
HAWTHORNE AVENUE PACO DRIVE BENVENUE AVENUE CAMPBELL AVENUE COMPRESSIONAL STE STE STE STE STE STE CAMPBELL AVENUE CAMPBELL AVENUE COMPRESSIONAL COMPRESSIONAL

 $\frac{\text{VICINITY MAP}}{\text{NOT TO SCALE}}$

LOS ALTOS, CALIFORNIA

CUESTA DRIVE NEIGHBORHOOD TRAFFIC CALMING 95% SUBMITTAL NOVEMBER, 2019



KEY MAP

SCALE: 1" = 200'

BASIS OF BEARINGS

HORIZONTAL COORDINATES ARE BASED ON CALIFORNIA STATE PLANE ZONE 3 UTILIZING THE CALIFORNIA SURVEYING AND DRAFTING SUPPLY REAL-TIME NETWORK. DATA WAS COLLECTED IN NOVEMBER 2018.

BENCHMARK

BRASS DISK ON TOP OF CONCRETE NORTHEASTERN
HEADWALL LOCATED AT THE NORTHWEST END OF SAID
HEADWALL ON HALE CREEK BRIDGE AT COVINGTON ROAD.
CITY OF LOS ALTOS.

SCVWD BM 350 ELEVATION (NAVD88) FEET: 174.20

DIG ALERT



AT LEAST 2 DAYS BEFORE YOU DIG

REVISIONS

NO DATE ITEM

DRAWING INDEX

SHEET TITLE T-01 2, 3 GN-01, GN-02 DM-01 TO DM-09 4-12 13-21 L-01 TO L-09 22-24 G-01 TO G-03 25, 26 D-01, D-02 D-03 27 28, 29 D-04, D-05 D-06

CONTENT
TITLE SHEET
GENERAL NOTES
DEMOLITION PLANS
LAYOUT PLANS
GRADING & DRAINAGE PLANS
CONSTRUCTION DETAILS
SIGNING DETAILS
CITY STANDARD DETAILS
CONSTRUCTION BMP'S

PROJECT OWNER

CITY OF LOS ALTOS 1 N. San Antonio Road Los Altos, CA 94022 www.losaltosca.gov

PROJECT CONSULTANTS

Alta Planning + Design, Inc. 304 12th Street, Suite 2A Oakland, CA 940607 T: 510.540.5008 F: 510.788.6485 www.altaplanning.com


PROJECT SURVEYOR

Wood Rogers, Inc.
4670 Willow Road, Suite 125
Pleasanton, CA 94588
T: 925.847.1556
F: 925.847.1557
www.woodrogers.com

DESIGNED:	JW
REVIEWED:	SF
DRAWN:	JP
2018-248	11/11/2019
PROJECT NO.	DATE
NTS SCALE	18-248-Title



304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008





P NOT TOR CONSTRUCTION

CUESTA DRIVE
TRAFFIC CALMING
CITY PROJECT No. XXXXXXX

Los Altos, California

TITLE SHEET

SHEET NO.

T-01

1 of 30

GENERAL NOTES:

- 1. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATIONS OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL COORDINATE WITH THE APPROPRIATE UTILITY COMPANY AS REQUIRED. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (U.S.A.) AT 1-800-227-2600 (OR DIAL 811) 72 HOURS PRIOR TO COMMENCING DEMOLITION OR EXCAVATION.
- 2. CONTRACTOR TO CONFIRM IF TRUCKS/EQUIPMENT CAN ACCESS SITE. IF TREE BRANCHES ARE AN OBSTRUCTION, THE CONTRACTOR SHALL REMOVE THE BRANCHES IN THE PRESENCE OF THE CITY ARBORIST.
- 3. THE CONTRACTOR SHALL COMPLY WITH ALL STATE, COUNTY, AND CITY LAWS AND ORDINANCES, REGULATIONS OF THE DEPARTMENT OF INDUSTRIAL RELATIONS, STATE CONSTRUCTION SAFETY ORDERS. AND CAL/OSHA. THIS REQUIREMENT SHALL BE MADE TO APPLY AT ALL TIMES
- 4. REQUIREMENTS FOR ALLOWABLE WORK HOURS AND TRAFFIC CONTROL ARE IN THE PROJECT SPECIFICATIONS.
- 5. THE CONTRACTOR SHALL PROVIDE FOR CONTINUOUS INGRESS AND EGRESS TO ALL PRIVATE PROPERTIES ADJACENT TO THE WORK THROUGHOUT THE PERIOD OF CONSTRUCTION UNLESS OTHERWISE SHOWN.
- 6. THE CONTRACTOR SHALL LOCATE, REFERENCE, AND SET SUFFICIENT MARKS FOR ALL EXISTING UTLITY BOXES, MANHOLE COVERS, MONUMENT LIDS, ETC., PRIOR TO ANY DEMOLITION OR PAVING WORK WITHIN THE PROJECT LIMITS AND SHALL REMOVE THE MARKS UPON COMPLETION OF THE WORK.
- 7. THE FINAL ADJUSTMENT TO FINISHED GRADE OF ALL FRAMES, COVERS, AND MANHOLES SHALL BE MADE FOLLOWING PLACEMENT OF THE TOP LAYER OF ASPHALT CONCRETE UNLESS OTHERWISE NOTED.
- 8. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CITY OF LOS ALTOS STANDARD DRAWINGS, THE CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, DATED 2014, REVISION 4. AND THE CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS AND STANDARD PLANS, DATED 2018, INCLUDING ALL PUBLISHED REVISIONS.
- 9. THE ENGINEER ASSUMES NO RESPONSIBILITY BEYOND THE ADEQUACY OF THE DESIGN CONTAINED HEREIN. THE CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY, THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND THAT THE CONTRACTOR SHALL DEFEND, IDEMNIFY AND HOLD THE OWNER AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY IN CONNECTION WITH THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT WRITTEN AUTHORIZATION FROM THE CITY.
- 11. THE CONTRACTOR IS RESPONSIBLE FOR MATCHING EXISTING STREETS, SURROUNDING LANDSCAPE, AND ALL OTHER EXISTING CONDITIONS WITH A SMOOTH TRANSITION IN PAVING, CURBS, GUTTERS, SIDEWALKS, GRADING, ETC., AND TO AVOID ANY ABRUPT OR APPARENT CHANGES IN GRADES OR CROSS SLOPES, LOW SPOTS, AND HAZARDOUS CONDITIONS.
- 12. THE CONTRACTOR SHALL NOTIFY ALL TRANSIT AGENCIES, TRASH COLLECTION AGENCY, AND EMERGENCY SERVICES OF THE CONSTRUCTION SCHEDULE TO ALLOW COORDINATION.
- 13. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ANY DAMAGES TO THE SITE OR SURROUNDING AREA AS A RESULT OF THE CONTRACTOR'S WORK OR OPERATIONS. EXISTING CURB, GUTTER, AND OTHER IMPROVEMENTS THAT ARE DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 14. ANY STREET SIGNS AND STREET SIGN POSTS NOT IDENTIFIED WITHIN THESE PLANS THAT EXIST WITHIN THE PROJECT EXTENTS SHALL BE PROTECTED IN PLACE, OR ARE TO REMAIN, UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER.
- 15. ANY EXISTING PAVEMENT MARKINGS AND PAVEMENT STRIPING NOT IDENTIFIED WITHIN THESE PLANS THAT EXIST WITHIN THE PROJECT EXTENTS SHALL BE PROTECTED IN PLACE, OR ARE TO REMAIN, UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER.

DIG ALERT DIAL TOLL FREE



AT LEAST 2 DAYS BEFORE YOU DIG

REVISIONS

TEMPORARY EROSION CONTROL NOTE:

CONTRACTOR SHALL PROVIDE TEMPORARY STORM WATER POLLUTION CONTROL DURING CONSTRUCTION PER SANTA CLARA VALLEY URBAN RUNOFF POLLUTION PREVENTION PROGRAM CONSTRUCTION BEST MANAGEMENT PRACTICES (SEE SHEET D-06). PROVIDE DRAINAGE INLET PROTECTION AT STORM DRAINS LOCATED WITHIN 500' OF PROJECT EXTENTS PER CALTRANS STD. PLAN T62. CONTRACTOR TO VERIFY ALL STORM WATER DRAIN INLET LOCATIONS

UTILITY NOTE

THE TYPES, LOCATIONS, SIZES AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THIS TOPOGRAPHIC SURVEY ARE APPROXIMATE AND WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS, AND DEPTHS OF SUCH UNDERGROUND UTILITIES. THE ENGINEER CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES WHICH MAY BE ENCOUNTERED, BUT WHICH ARE NOT SHOWN ON THIS SURVEY.

PROPOSED WORK LEGEND:

PCC SECTION

DETECTABLE WARNING SURFACE

D.G. SECTION

A.C. SECTION

DEMOLITION LEGEND:

SB REMOVE EXISTING STRIPING BY SANDBLASTING. ALL DEBRIS SHALL BE REMOVED BY THE END OF EACH WORKDAY.

---- | SC | SAWCUT EXISTING PAVEMENT SURFACE. ALL DEBRIS SHALL BE REMOVED BY THE END OF EACH WORKDAY.



P PROTECT IN PLACE EX. STRIPING AND PAVEMENT MARKINGS



GRIND 3" OF EXISTING ASPHALT PAVEMENT SURFACE (PER PLANS)



CLEAR AND GRUB



REMOVE AND DISPOSE OF A.C. AND BASE MATERIAL



REMOVE AND DISPOSE OF CONCRETE AND BASE MATERIAL

REMOVE AND DISPOSE OF EXISTING CURB / BERM (PER PLANS)

TTT

LIMITS OF MICROSURFACING

ABBREVIATIONS:

AGGREGATE BASE A.C. ASPHALT CONCRETE BEGINNING OF CURVE BOW BACK OF WALK

CALTRANS CALIFORNIA DEPARTMENT OF TRANSPORTATION

CB CATCH BASIN CONT. CONTINUED CENTERLINE STORM DRAIN INLET DRIVEWAY

EAST **EASTING** END OF CURVE **EDGE OF PAVEMENT**

EX. **EXISTING** FINISHED GRADE FIRE HYDRANT **FLOWLINE** GAS UTILITY

HOT MIXED ASPHALT INVERT ELEVATION **JOINT POLE** LINEAR FEET (FOOT)

MAX. MAXIMUM **MANHOLE** MINIMUM NORTH NORTHING NOT TO SCALE ORIGINAL GROUND OVERHEAD UTILITY ON CENTER

PB PULLBOX PCC PORTLAND CEMENT CONCRETE POINT OF REVERSE CURVE **PVC** POLYVINYL CHLORIDE PIPE RIGHT (DIRECTIONAL)

RADIUS REINFORCED CEMENT PIPE

RIM ELEVATION RIGHT OF WAY SOUTH STORM DRAIN SANITARY SEWER

STATION STANDARD

SCVURPPP SANTA CLARA URBAN RUNOFF POLLUTION

PREVENTION PROGRAM


SIDEWALK TC TOP OF CURB TRAFFIC SIGNAL TYP. **TYPICAL** VLT **VAULT** WATER UTILITY

WEST

DESIGNED: **REVIEWED:** NO DATE ITEM 11/11/2019 DATE 2018-248 PROJECT NO. 18-248-General Notes FILE



304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008







CUESTA DRIVE TRAFFIC CALMING CITY PROJECT No. XXXXXXX

GENERAL NOTES

GN-01


SHEET NO.

Los Altos, California

2 of 30

ALIGNMENT LINE DATA					
LINE#	ALIGNMENT	LENGTH	BEARING	Beg. STA	END STA
L1	С	30.00	S52°45'55.69"E	1+00.00	1+30.00
L2	С	2967.48	S88°59'40.69"E	5+32.52	35+00.00
L3	А	275.00	S1°00'19.31"W	6+33.83	9+08.83
L4	А	2725.00	S88°59'40.69"E	10+26.64	37+51.64
L5	СВ	1000.00	S0°55'13.92"W	19+51.24	29+51.24

ALIGNMENT CURVE DATA						
CURVE#	ALIGNMENT	RADIUS	LENGTH	DELTA	Beg. STA	END STA
C1	С	636.58	402.52	36°13'45.00"	1+30.00	5+32.52
C2	А	75.00	117.81	90°00'00.00"	9+08.83	10+26.64



BASIS OF BEARINGS

HORIZONTAL COORDINATES ARE BASED ON CALIFORNIA STATE PLANE ZONE 3 UTILIZING THE CALIFORNIA SURVEYING AND DRAFTING SUPPLY REAL-TIME NETWORK. DATA WAS COLLECTED IN NOVEMBER 2018.


BENCHMARK

BRASS DISK ON TOP OF CONCRETE NORTHEASTERN HEADWALL LOCATED AT THE NORTHWEST END OF SAID HEADWALL ON HALE CREEK BRIDGE AT COVINGTON ROAD. CITY OF LOS ALTOS.

SCVWD BM 350 ELEVATION (NAVD88) FEET: 174.20

alta NO DATE ITEM 304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008

PLANNING + DESIGN www.altaplanning.com





CUESTA DRIVE TRAFFIC CALMING CITY PROJECT No. XXXXXXX

SHEET NO.

GENERAL NOTES


GN-02 3 of 30


DESIGNED:


REVIEWED:


2018-248 PROJECT NO.


Los Altos, California












NOTES:

- 1. FOR NOTES, LEGEND AND ABBREVIATIONS SEE SHEET
- 2. FOR LAYOUT, GRADING & DRAINAGE DRAWING NUMBERS AT THIS LOCATION, SEE SHEET T-1, KEY MAP.
- 3. FOR ALIGNMENT CURVE AND LINE DATA, SEE SHEET GN-02.

DEMOLITION LEGEND:


LEGEND FOR THIS SHEET ONLY.
LEGEND ITEMS DO NOT NECESSARILY APPEAR ON EVERY SHEET.

- SB REMOVE EXISTING STRIPING BY SANDBLASTING. ALL DEBRIS SHALL BE REMOVED BY THE END OF EACH WORKDAY.
- P PROTECT IN PLACE EX. STRIPING AND PAVEMENT MARKINGS
- GRIND 3" OF EXISTING ASPHALT PAVEMENT SURFACE (PER PLANS)




SHEET NO.

DESIGNED:	JW
REVIEWED:	SF
DRAWN:	JP, EK
2018-248 PROJECT NO.	11/11/2019 DATE
1"=20' SCALE	18-248-Demo Plans FILE



PLANNING + DESIGN
www.altaplanning.com

304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008






PRI TOR CONSTRUCTION =


CUESTA DRIVE
TRAFFIC CALMING
CITY PROJECT No. XXXXXXX


Los Altos, California


DEMOLITION PLANS


DM-05 8 of 30























NOTES:

- 1. FOR NOTES, LEGEND AND ABBREVIATIONS SEE SHEET GN-1
- 2. FOR DEMOLITION, GRADING & DRAINAGE DRAWING NUMBERS AT THIS LOCATION, SEE SHEET T-1, KEY MAP.
- 3. FOR ALIGNMENT CURVE AND LINE DATA, SEE SHEET GN-02.

CONSTRUCTION NOTES:


CONSTRUCTION NOTES FOR THIS SHEET ONLY.
CONSTRUCTION NOTES DO NOT NECESSARILY APPEAR ON EVERY SHEET.

- 1 CONSTRUCT SPEED HUMP PER DETAIL 1, SHEET D-01
- CONSTRUCT SPEED TABLE RAISED CROSSWALK PER DETAIL 3, SHEET D-01
- 28 INSTALL CONTINENTAL STYLE HIGH VISIBILITY CROSSWALK PER DETAIL 1, SHEET D-02
- D## INSTALL PAVEMENT MARKING PER CALTRANS STD PLANS A10A 10AE, PER DETAIL ##

SIGNAGE NOTES:


SIGNAGE NOTES FOR THIS SHEET ONLY.
SIGNAGE NOTES DO NOT NECESSARILY APPEAR ON EVERY SHEET.
SEE SHEET D-03 FOR SIGNING SCHEDULES.

- 2 FURNISH AND INSTALL NEW SINGLE SIDED SIGN PER CITY OF LOS ALTOS STANDARD DETAIL SU-17, AND SHEET D-05
- 6 FURNISH AND INSTALL NEW DOUBLE SIDED SIGN PER CITY OF LOS ALTOS STANDARD DETAIL SU-17, AND SHEET D-05
- $\langle P \rangle$ PROTECT IN PLACE EXISTING SIGN(S) AND POST



SHEET NO.

DESIGNED:	JW
REVIEWED:	<u>SF</u>
DRAWN:	JP, EK
2018-248 PROJECT NO.	11/11/2019 DATE
1"=20'	18-248-Layouts













CUESTA DRIVE
TRAFFIC CALMING
CITY PROJECT No. XXXXXXX


Los Altos, California


LAYOUT PLANS


L-05 17_o 30















Los Altos, California

 $23 \, \text{OF} \, 30$

Drainage Plans FILE

PLANNING + DESIGN

www.altaplanning.com



CITY PROJECT No. XXXXXXX


Los Altos, California

DRAINAGE PLANS

24 of **30**

PLANNING + DESIGN

www.altaplanning.com



FILE PATH: P:\18-248 Los Altos Cuesta Traffic Calmin

DESIGNED:

REVIEWED:

2018-248 PROJECT NO.

DRAWN:

REVISIONS


JP, EK

11/11/2019 DATE

18-248-Details FILE NO DATE ITEM

PLANNING + DESIGN www.altaplanning.com

304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008








CUESTA DRIVE
TRAFFIC CALMING
CITY PROJECT No. XXXXXXX

Los Altos, California

CONSTRUCTION DETAILS

D-01 25_{of} 30

SHEET NO.



WARNING SIGN SCHEDULE					
KEY	SIZE	SIGN & COLOR			
S1-1	30" X 30"	BACKGROUND: YELLOW BORDER: BLACK LEGEND: BLACK	W16-7P	24" X 12"	NEXT XXX FT BACKGROUND: YELLOW BORDER: BLACK LEGEND: BLACK
W3-1	30" X 30"	BACKGROUND: YELLOW BORDER: BLACK LEGEND: RED & BLACK	W16-7P	24" X 12"	BACKGROUND: YELLOW BORDER: BLACK LETTERING: BLACK
W3-3	30" X 30"	BACKGROUND: YELLOW BORDER: BLACK LEGEND: RED, YELLOW, GREEN & BLACK	W16-9P	24" X 12"	BACKGROUND: YELLOW BORDER: BLACK LETTERING: BLACK
W4-4P	24" X 12"	CROSS TRAFFIC DOES NOT STOP BACKGROUND: YELLOW BORDER: BLACK LETTERING: BLACK	W16-15P	24" X 12"	BACKGROUND: YELLOW BORDER: BLACK LETTERING: BLACK
W13-1P (15MPH)	18" X 18"	BACKGROUND: YELLOW BORDER: BLACK LETTERING: BLACK	W17-1	30" X 30"	SPEED HUMP BACKGROUND: YELLOW BORDER: BLACK LETTERING: BLACK


REGULATOR	REGULATORY SIGN SCHEDULE			
KEY	SIZE	SIGN & COLOR		
R1-1	30" X 30"	BACKGROUND: RED BORDER: WHITE LETTERING: WHITE		
R1-3P	36" X 24"	BACKGROUND: RED BORDER: WHITE LETTERING: WHITE		
R4-7	24" X 36"	BACKGROUND: WHITE BORDER: BLACK LEGEND: BLACK		

GUIDE SIGN SCHEDULE			
KEY	SIZE	SIGN & COLOR	
D11-1	24" X 18"	BACKGROUND: GREEN LETTERING: WHITE BORDER/LEGEND: WHITE	

NOTES:

- 1. SIGN AND POST INSTALLATION TO CONFORM TO CITY OF LOS ALTOS STANDARD DETAILS SU-15, SU-16, AND SU-17, SEE SHEET D-05.
- 2. STREET SIGN FACES TO CONFORM TO CITY OF LOS ALTOS STANDARD DETAILS SU-15, SEE SHEET D-05.
- 3. SIGN S1-1 (AND PLAQUES WITH SIGN S1-1) SHALL BE YELLOW-GREEN IN COLOR. SIGN POSTS WITH SIGN S1-1 SHALL HAVE YELLOW-GREEN SIGN POLE REFLECTOR ON THE POLE SHAFT. REFLECTOR SHALL READ "SCHOOL".

DESIGNED:	JW
REVIEWED:	SF
DRAWN:	JP
2018-248 PROJECT NO.	11/11/2019 DATE
NTS SCALE	18-248-Details










CUESTA DRIVE TRAFFIC CALMING CITY PROJECT No. XXXXXXX


Los Altos, California


CONSTRUCTION **DETAILS**

SHEET NO. D-03 **27** of **30**

304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008







RELEVANT CITY STANDARD CONSTRUCTION DETAILS FOR PROJECT WORK (SU-6, SU-8,LI-9)

NTS


SHEET NO.

DESIGNED:	JW
REVIEWED:	SF
DRAWN:	JP, EK
2018-248 PROJECT NO.	11/11/2019 DATE
NTS SCALE	18-248-Details


REVISIONS

NO DATE ITEM

alta 304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008 PLANNING + DESIGN www.altaplanning.com









CUESTA DRIVE TRAFFIC CALMING CITY PROJECT No. XXXXXXX


Los Altos, California

CONSTRUCTION **DETAILS**

D-04 28 of 30







RELEVANT CITY STANDARD SIGNING DETAILS (SU-15, SU-16, SU-17)

NTS

SHEET NO.

DESIGNED: JW

REVIEWED: SF

DRAWN: JP, EK


2018-248 11/11/2019
PROJECT NO. DATE

NTS 18-248-Details
SCALE FILE

NO DATE ITEM



304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008





PRICTION =

CUESTA DRIVE
TRAFFIC CALMING
CITY PROJECT No. XXXXXXX

Los Altos, California


CONSTRUCTION DETAILS

D-05 29_o 30

Construction Best Management Practices (BMPs)

Construction projects are required to implement year-round stormwater BMPs.

Materials & Waste Management



Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use.
- ☐ Use (but don't overuse) reclaimed water for dust control.
- ☐ Ensure dust control water doesn't leave site or discharge to storm drains.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with City, County, State and Federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. A plastic liner is recommended to prevent leaks. Never clean out a dumpster by hosing it down on the construction site.
- ☐ Place portable toilets away from storm drains. Make sure they are in good working order. Check frequently for leaks.
- ☐ Dispose of all wastes and demolition debris properly. Recycle materials and wastes that can be recycled, including solvents, waterbased paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.
- ☐ Keep site free of litter (e.g. lunch items, cigarette butts).
- ☐ Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

Equipment Management & Spill Control




Maintenance and Parking

- ☐ Designate an area of the construction site, well away from streams or storm drain inlets and fitted with appropriate BMPs, for auto and equipment parking,
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- ☐ Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- ☐ Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report significant spills to the appropriate local spill response agencies immediately. If the spill poses a significant hazrd to human health and safety, property or the environment, you must report it to the State Office of Emergency Services. (800) 852-7550 (24

Earthmoving



Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, plant temporary vegetation for erosion control on slopes or where construction is not immediately planned
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (i.e. silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.


Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash.
- ☐ If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not distrurbed by construction activities.

Landscaping

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

Concrete Management and Dewatering




Concrete Management

- ☐ Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area onsite, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

Dewatering

- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible, send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer, call your local wastewater treatment plant.
- ☐ Divert run-on water from offsite away from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.

Paving/Asphalt Work




Paving

- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or properly dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.

Painting & Paint Removal



Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.



Storm drain polluters may be liable for fines of up to \$10,000 per day!

DESIGNED: 11/11/2019 DATE 18-248-Details FILE NTS SCALE

REVISIONS NO DATE ITEM



304 12TH ST, SUITE 2A OAKLAND, CA 94607 p:510.540.5008





PRINTERCONSTRUCT

CUESTA DRIVE TRAFFIC CALMING **CITY PROJECT No. XXXXXXX**

Los Altos, California

CONSTRUCTION BMP'S

D-06 $30 \, \text{OF} \, 30$

SHEET NO.

REVIEWED: DRAWN: 2018-248 PROJECT NO. alta