


FRONT PERSPECTIVE



	PLANNING DATA		ZONING CO	ZONING COMPLIANCE			SHEET INDEX		
	PROJECT ADDRESS:	99 DOUD DRIVE, LOS ALTOS, CALIFORNIA		Existing	Proposed	Allowed/Required	ARCHITECTURAL		
	PROJECT DESCRIPTION:	IT IS INTENDED TO DEMOLISH AN EXISTING 1-STORY RESIDENCE WITH DETACHED GARAGE AND ASSOCATED OUTBUILDINGS AND TO CONSTRUCT A NEW 4,889 SF 2-STORY WOOD FRAMED R-3	LOT COVERAGE: Land area covered by all structures that are over 6 feet in height	<u>3,893.0</u> square feet ( <u>17.2</u> %)	$\frac{4,634.7}{(\underline{20.5}\%)}$ square feet	<u>6,777.3</u> square feet ( <u>30.0</u> %)	A0 COVER SHEET, PROJECT SUMMARY A1 STREETSCAPE A2 NEIGHBORHOOD SITE CONTEXT	, VICINITY MAP	
		RESIDENCE W/ ATTACHED GARAGE AND PARTIAL 1,599 SF BASEMENT. SITE IMPROVEMENTS INCLUDE A NEW 20'X48' POOL AND 117 SF CABANA BUILDING.	FLOOR AREA: Measured to the outside surfaces of	1st Flr: <u>3,379</u> sq ft 2 <sup>nd</sup> Flr: <u>-</u> sq ft <b>Total: <u>3,379</u> sq ft</b>	1st Flr <u>: 3,470.3</u> sq ft 2 <sup>nd</sup> Flr <u>: 1,535.7</u> sq ft Total: <u>5,006.0</u> sq ft	5,009.1_square feet	A3 AREA CALCULATIONS A4 DEMOLITION & TREE PROTECTION P A5 SITE PLAN A6 FIRST FLOOR PLAN A7 SECOND FLOOR PLAN	LAN	
	APN:	170-31-009	exterior walls	( <u>15%)</u>	( <u>22.1</u> %)		A8 LOWER LEVEL PLAN		
}	ZONING:	R1-10 SINGLE FAMILY DISTRICT	SETBACKS:				A10 CABANA PLANS		
	OCCUPANCY:	R-3/ U	Front	<u>43 f</u> eet	<u>40.0</u> feet	<u>40</u> feet	A11 EXISTING EXTERIOR ELEVATIONS A12 EXTERIOR ELEVATIONS		
8	LOT AREA:	22,591 SQ.FT. / 0.52 ACRES	Rear Right side $(1^{st}/2^{nd})$	<u>98 f</u> eet <u>10 fe</u> et <u>/ - feet</u>	<u>109.1</u> 6 feet <u>16.45</u> feet/ <u>18.29 f</u> eet	<u>25</u> feet <u>10</u> feet <u>/17.5</u> feet	A13 EXTERIOR ELEVATIONS A14 CABANA ELEVATIONS AND SECTION	S	
N °	HISTORIC STATUS:	NO	Left side $(1^{st}/2^{nd})$	<u>19 f</u> eet <u>- feet</u>	<u>10.29</u> feet/ <u>18.29</u> feet	<u>10</u> fee <u>t/17.5</u> feet	A15 SECTIONS A16 SECTIONS & TYPICAL DETAILS A17 MATERIAL COLOR BOARD		
	FLOOD ZONE:	NO	Height:	<u>_17.0 f</u> eet	<u>24.0 f</u> eet	<u>_27.0 f</u> eet	CIVIL		
	STORIES:	2	SQU	ARE FOOTAGE H	BREAKDOWN		C-1.0 TITLE SHEET C-2.0 OVERALL SITE PLAN		
PCLC 11 12 13	FIRE SPRINKLERS:	YES		EXISTING	PROPOSED	TOTAL PROPOSED	C-2.1 GRADING AND DRAINAGE PLAN ER-1 EROSION CONTROL PLAN		
<u>36</u>	MAXIMUM LOT COVERAGE: 2 STORY DEVELOPMENT	6,777.3 SQ. FT. (30% OF LOT AREA)	HABITABLE LIVING AREA: Includes habitable basement areas	<u>2,517</u> square feet	<u>4,088</u> square feet	<u>6,605</u> square feet	ER-2 EROSION CONTROL DETAILS SU-1 SURVEY SHEET		
GLA 37 5	MAX. FLOOR AREA (MFA):	5,009.1 SQ. FT. (3,850 + 10% [LOT AREA-11,000])	<b>NON- HABITABLE AREA:</b> Does not include covered porches or open structures	<u> </u>	<u>(-) 90</u> square feet	<u> </u>	LANDSCAPE L.1 LANDSCAPE PLAN L.2 IRRIGATION PLAN		
	HEIGHT LIMIT:	27 FT FROM NATURAL GRADE		LOT CALCULA	TIONS		L.3 IRRIGATION GENERAL NOTES NAD S L.4 IRRIGATION DETAILS	PECIFICATIONS	
	DAYLIGHT PLANE:	11 FT AT SIDE PROPERTY LINE, THEN SLOPE UPWARD 25° FROM THE HORIZONTAL	NET LOT AREA:		22,591.0 square feet				
90 ₩ ₩ 77.41 \$ <u>42</u> §	ACCESSORY STRUCTURE:	800 SQ. FT. & 12 FT HEIGHT IF LOCATED IN REAR YARD SETBACK	<b>FRONT YARD HARDSCAPE AR</b> Hardscape area in the front yard setback		<u>1,203.0</u> square feet (	( <u>49.</u> 3 %)			
	REQUIRED PARKING:	120 SQ. FT. & 6 FT HEIGHT IF LOCATED IN SIDE YARD SETBACK 2 SPACES @ MAIN RESIDENCE (1 SPACE TO BE COVERED)	LANDSCAPING BREAKDOWN:	Existing softscape (un New softscape (new c	(existing and proposed): idisturbed) area: or replaced landscaping) a , cabana, porches, lightwo	<u>6,045</u> sq ft <u>0</u> sq ft rea: <u>11,399</u> sq ft ells) 5,147 sq ft			
	BASEMENT:	NOT TO EXTEND BEYOND THE FIRST FLOOR							
	NOTE: SEE SHEET A3 FOR AREA I	DIAGRAMS AND CALCULATION BREAKDOWN							EV 12.04.19 EV 11.14.19
								Date:	9.26.1
THE	FAIR RE	SIDENCE						Job:	190
	99 DOUD D					CO	VER SHEET	A	$\cap$

LOS ALTOS, CALIFORNIA





115 DOUD DRIVE





# 134 DOUD DRIVE





# 120 DOUD DRIVE



99 DOUD DRIVE

83 DOUD DRIVE



100 DOUD DRIVE



84 DOUD DRIVE

THE FAIR RESIDENCE 99 DOUD DRIVE LOS ALTOS, CALIFORNIA

# STREETSCAPE

## 9.26.19 1906


A1


# 72 DOUD DRIVE

REV 11.14.19



34 AZALEA WAY














61 DOUD DRIVE






34)

















LOT COVERAGE						
FIRST FLOOR ARE	AS					
F1 - F13			3353.3 SF			
CABANA AREAS						
A1 - A2			117.0 SF			
I	PORCH	AREAS				
NAME	DIMEN	ISIONS	AREA			
P1	4'-6	" x 8'	36.0 SF			
P2	7'	x 8'	56.0 SF			
P3	17' x	21'-3"	361.2 SF			
P4	11'-6"	x 3'-6"	40.3 SF			
P5	14'-6"	x 13'-3"	192.1 SF			
P6	20'	x 9'	180.0 SF			
P7	18'-6	" x 16	296.0 SF			
P8	0'-6"	x 2'-9"	1.4 SF			
P9	0'-6"	x 2'-9"	1.4 SF			
			1164.4 SF			
<b>TOTAL LOT COVERAGE:</b> 4634.7 SF < 6777.3 SF						

LOWER LEVEL AREA						
NAME	DIMENSIONS	AREA				
L1	39' x 41'	1599.0 SF				
LIGHTCOURT	30'-6" x 13'-3"	404.0 SF				
LIGHTWELL	7' x 15'-6"	108.5 SF				
EXEMPT 2111.5 SF						

FIRST FLOOR AREA					
NAME	DIMENSIONS	AREA			
F1	24' x 25'	600.0 SF			
F2	16' x 8'	128.0 SF			
F3	13'-6" x 11'-9"	158.6 SF			
F4	11' x 8'	88.0 SF			
F5	9' x 2'	18.0 SF			
F6	47' x 13'-3"	622.8 SF			
F7	1' x 10'	10.0 SF			
F8	38' x 17'-6"	665.0 SF			
F9	34'-6" x 8'	276.0 SF			
F10	15'-6" x 12'-3"	189.9 SF			
F11	39' x 14'-6"	565.5 SF			
F12	14' x 1'-9"	24.5 SF			
F13	7' x 1'-0"	7.0 SF			
SUBTOTAL:		3353.3 SF			


FLOOR AREAS

## SECOND FLOOR AREA

NAME	DIMENSIONS	AREA			
S1	47' x 13'-3"	622.8 SF			
S2	20'-6" x 7'-6"	153.8 SF			
S3	6' x 2'	12.0 SF			
S4	19'-6" x 20'-3"	394.8 SF			
S5	8' x 10'	80.0 SF			
S6	6' x 1'-6"	9.0 SF			
S7	21'-6" x 12'-3"	263.3 SF			
SUBTOTAL:		1535.7 SF			
CABANA AREA					
NAME	DIMENSIONS	AREA			
• •					

A1	13' x 4'-9"	61.8 SF
A2	13' x 4'-3"	55.2 SF
SUBTOTAL:	117.0 SF	
TOTAL FLOOR ARE	E <b>A:</b> 5006	.0 SF < 5009.1 SF

# THE FAIR RESIDENCE 99 DOUD DRIVE LOS ALTOS, CALIFORNIA




- BE MOUNTED ON STEEL POSTS DRIVEN APPROXIMATELY 2 FEET
- FENCING POSTS MUST BE LOCATED A MAXIMUM OF 10 FEET ON
- MATERIALS, VEHICLES, OR EQUIPMENT.
- PROTECTIVE FENCING MUST NOT BE MOVED, EVEN TEMPORARILY, AND MUST REMAIN IN PLACE UNTIL ALL CONSTRUCTION IS
- TREE PROTECTION SIGNAGE SHALL BE MOUNTED TO ALL INDIVIDUAL TREE PROTECTION FENCES.


321-0202, A PROJECT ARBORIST SHOULD SUPERVISE ANY EXCAVATION ACTIVITIES WITHIN THE TREE PROTECTION ZONE OF THESE TREES.


- ANY ROOTS EXPOSED DURING CONSTRUCTION ACTIVITIES THAT ARE LARGER THAN 2 INCHES IN DIAMETER SHOULD NOT BE CUT OR DAMAGED UNTIL THE PROJECT ARBORIST HAS AN OPPORTUNITY TO ASSESS THE IMPACT THAT REMOVING THESE ROOTS COULD HAVE ON THE TREES.
- WEEKS DURING THE DRY MONTHS.
- MULCH SHOULD COVER ALL BARE SOILS WITHIN THE TREE PROTECTION FENCING. THIS MATERIAL MUST BE 6-8 INCHES IN DEPTH AFTER SPREADING. WHICH MUST BE DONE BY HAND. COURSE WOOD CHIPS ARE PREFERRED BECAUSE THEY ARE ORGANIC AND DEGRADE NATURALLY OVER TIME.
- LOOSE SOIL AND MULCH MUST NOT BE ALLOWED TO SLIDE DOWN SLOPE TO COVER THE ROOT ZONES OR THE ROOT COLLARS OF PROTECTED TREES.
- THERE MUST BE NO GRADING, TRENCHING, OR SURFACE SCRAPING INSIDE THE DRIPLINES OF PROTECTED TREES, UNLESS SPECIFICALLY
- TRENCHES FOR ANY UNDERGROUND UTILITIES (GAS, ELECTRICITY, WATER, PHONE, TV CABLE, ETC.) MUST BELOCATED OUTSIDE THE ARBORIST. ALTERNATIVE METHODS OF INSTALLATION MAY BE
- LANDSCAPE IRRIGATION TRENCHES MUST BE LOCATED AMINIMUM DISTANCE OF 10 TIMES THE TRUNK DIAMETER FROM THE TRUNKS OF PROTECTED TREES UNLESS OTHERWISE NOTEDAND APPROVED BY THE ARBORIST.


MATERIALS MUST NOT BE STORED, STOCKPILED, DUMPED, OR



	EXIS	TING TREE	S (SEE ARBORIS	ST TREE SURVEY DATA)	
EXCAVATED SOIL MUST NOT BE PILED OR DUMPED, EVEN TEMPORARILY, INSIDE THE DRIPLINES OF PROTECTED TREES.	NUMBER	COMMON NAME	DIAMETER	WIDTH / HEIGHT	RETA
LANDSCAPE MATERIALS (COBBLES, DECORATIVE BARK, STONES,	1	PURPLE LEAF PLUM	4.5"	12' / 12'	REM
FENCING, ETC.) MUST NOT BE INSTALLED DIRECTLY IN CONTACT WITH THE BARK OF TREES BECAUSE OF THE RISK OF SERIOUS DISEASE INFECTION.	2	PURPLE LEAF PLUM	9"	24' / 24'	REM
LANDSCAPE IRRIGATION SYSTEMS MUST BE DESIGNED TO AVOID	3	LIQUID AMBAR	15"	30' / 32'	REM
WATER STRIKING THE TRUNKS OF TREES, ESPECIALLY OAK TREES.	4	ASH	28"	42' / 32'	RET
ANY PRUNING MUST BE DONE BY A COMPANY WITH AN ARBORIST CERTIFIED BY THE ISA (INTERNATIONAL SOCIETY OF ARBORICULTURE) AND ACCORDING TO ISA, WESTERN CHAPTER	5	HOLLY/ VARIEGATED	8.5"	12' / 15'	REM
STANDARDS, 1998.	6	PITISPORUM TOBIRA	4",4",2"	8' / 10'	REM
ANY PLANTS THAT ARE PLANTED INSIDE THE DRIPLINES OF OAK TREES MUST BE OF SPECIES THAT ARE COMPATIBLE WITH THE ENVIRONMENTAL AND CULTURAL REQUIREMENTS OF OAKS TREES. A	7	PERSIMMON	9"	25' / 25'	REM
PUBLICATION DETAILING PLANTS COMPATIBLE WITH CALIFORNIA NATIVE OAKS CAN BE OBTAINED FROM THE CALIFORNIA OAK	8	PERSIMMON	9"	18' / 18'	REM
FOUNDATION'S 1991 PUBLICATION "COMPATIBLE PLANTS UNDER & AROUND OAKS" DETAILS PLANTS COMPATIBLE WITH CALIFORNIA NATIVE OAKS AND IS CURRENTLY AVAILABLE ONLINE AT:	9	BIRCH	4.5"	8' / 15'	REM
http://californiaoaks.org/wpcontent/uploads/2016/04/CompatiblePlantsUnder AroundOaks.pdf	10	REDWOOD	20"	16' / 48'	RET
	11	REDWOOD	20"	16' / 48'	RET
	12	SCHOLAR	11"	20' / 25'	RET
	13	COAST LIVE OAK	25"	35' / 35'	REM
	14	CRAPE MRTYLE	5",5",4"	8' / 14'	RET
	15	BIRCH	28"	20' / 43.5'	RET
	16	SAUCER MAGNOLIA	4", 5"	10' / 12'	REM
	•			· · · · · · · · · · · · · · · · · · ·	












2 A13 C A16 47' - 0" 7' - 0" 3' - 6" 11' - 6" 🦯 7' - 0" 7' - 0" 11' - 0" - - - - - -HIGH WINDOWS HIGH WINDOWS SHLVS SHLVS **TOILET** 6' x 3'-6" SHWR 15' - 0" CANTILEVERED BENCH \_7'-6" x 4'\_ 17' - 6" 8' - 0" 6' - 6" MASTER BEDROOM MASTER CLOSET 17' x 12'-3" 14' x 6' 🔶 ATTIC | ACCESS MASTER BATH KING 14' x 8'-3" 13' - 0"<sup>\_\_\_</sup> 2' - 0' DRSG. \_\_\_\_\_ EQ EQ -⊢TUB \_\_\_\_\_12'-6" x 5'-9" | \_\_\_\_\_ \_ \_ \_SL **SL** GAS FIREPLACE VANITY DRESSER г — <del>†</del> — KITCHEN
EXHAUST HOOD H \_\_\_\_\_ HIGH 18' - 6" WINDOW 6' - 0" 6' - 0"  $\longrightarrow$ B.I. QUEEN - SKYLIGHT LAUNDRY 7'-6" x 10'-6" **BEDROOM 201** \_ \_ \_ - ťo I.B 13' x 11'-9" 53' \_\_\_\_14' - 0"\_\_\_\_\_ 5' - 6" 8' - 0" \_\_\_\_\_W\_\_\_\_ \_D\_ SL \_ \_ \_ \_ \_ \_ \_ \_ \_ \_ **HALL 201** 5' WIDE . ູ<sub>ເ∿</sub>ີ¢L. 201ຸ WĊ ĀĀ BATH 201 —7' -6" x 7 ¦≓v/// || v/ // ;;;¢L. 202 \_\_\_\_\_ BEDROOM 202 13' x 11'-9" BATH 202 7'-2" x 7'-8" 13' - 6" 2 - 0" QUEEN  $\bigcirc$ - HIGH WINDOWS 3' - 3" 8' - 0" 8' - 0" 11' - 6" 27' - 6" 47' - 0" 2 A12 C A16


> THE FAIR RESIDENCE 99 DOUD DRIVE LOS ALTOS, CALIFORNIA


















# THE FAIR RESIDENCE 99 DOUD DRIVE LOS ALTOS, CALIFORNIA


3


A14


2/4/2019 6:41:21 PI















WWW.PACIFICPENINSULA.COM

LOS ALTOS, CALIFORNIA












WINDOW AND DOOR CLADDING



WOOD SIDING




WINDOW AND DOOR IMAGE











STANDING SEAM METAL ROOF



STANDING SEAM ROOF IMAGE



NATURAL STONE VENEER

# THE FAIR RESIDENCE 99 DOUD DRIVE LOS ALTOS, CALIFORNIA







MATERIAL COLOR

BOARD

WOOD TRIM COLOR

REV 11.14.19

A17

Job:

9.26.19 1906


## LEGEND

PROPOSED

## FYISTING

EXISTING	
	R\
· · ·	
SS	
W G	
P	
JT	
	· ~~>>
СВ	,
JB	
⊂ <sub>sdmh</sub>	
1	

E C




## BOUNDARY PROPERTY LINE **RETAINING WALL** LANDSCAPE RETAINING WALL RAINWATER TIGHTLINE SUBDRAIN LINE TIGHTLINE STORM DRAIN LINE SANITARY SEWER LINE WATER LINE GAS LINE PRESSURE LINE JOINT TRENCH SET BACK LINE CONCRETE VALLEY GUTTER EARTHEN SWALE CATCH BASIN JUNCTION BOX AREA DRAIN CURB INLET STORM DRAIN MANHOLE FIRE HYDRANT SANITARY SEWER MANHOLE STREET SIGN SPOT ELEVATION FLOW DIRECTION DEMOLISH/REMOVE BENCHMARK CONTOURS

DESCRIPTION

TREE TO BE REMOVED

TREE PROTECTION FENCING

MAXIMUM MANHOLE MINIMUM MONUMENT METERED RELEASE OUTLET NEW NUMBER NOT TO SCALE ON CENTER OVER PLANTING AREA PEDESTRIAN POST INDICATOR VALVE PUBLIC SERVICES EASEMENT PROPERTY LINE POWER POLE PUBLIC UTILITY EASEMENT POLYVINYL CHLORIDE RADIUS REINFORCED CONCRETE PIPE RIM ELEVATION RAINWATER RIGHT OF WAY SLOPE SEE ARCHITECTURAL DRAWINGS SANITARY STORM DRAIN STORM DRAIN MANHOLE SHEET SEE LANDSCAPE DRAWINGS SPECIFICATION SANITARY SEWER SANITARY SEWER CLEANOUT SANITARY SEWER MANHOLE STREET STATION STANDARD STRUCTURAL TELEPHONE TOP OF CURB TOP OF WALL TEMPORARY TOP OF PAVEMENT TOP OF WALL/FINISH GRADE TYPICAL VERTICAL CURVE VITRIFIED CLAY PIPE VERTICAL WITH WATER LINE WATER METER WELDED WIRE FABRIC




## **RETAINING WALL NOTES**

## ABBREVIATIONS

XX" TREE


AB	AGGREGATE BASE	LF
AC	ASPHALT CONCRETE	MAX
ACC	ACCESSIBLE	MH
AD	AREA DRAIN	MIN
BC	BEGINNING OF CURVE	MON.
B & D	BEARING & DISTANCE	MRO
BM BUB BW/FG	BENCHMARK BUBBLER BOX BOTTOM OF WALL/FINISH GRADE	(N) NO. NTS O.C.
CB C& G ଜୁ	CATCH BASIN CURB AND GUTTER CENTER LINE	0.0. 0/ (PA) PED
CPP CO	CORRUGATED PLASTIC PIPE (SMOOTH INTERIOR) CLEANOUT	PIV PSS 문
COTG	CLEANOUT TO GRADE	PP
CONC	CONCRETE	PUE
CONST	CONSTRUCT or -TION	PVC
CONC COR	CONCRETE CORNER	R
CY	CUBIC YARD	RCP
D	DIAMETER	RIM
DI	DROP INLET	RW
DIP	DUCTILE IRON PIPE	R/W
EA	EACH	S
EC	END OF CURVE	S.A.D.
EG	EXISTING GRADE	SAN
EL	ELEVATIONS	SD
EP	EDGE OF PAVEMENT	SDMH
EQ	EQUIPMENT	SHT
EW	EACH WAY	S.L.D.
(E)	EXISTING	SPEC
FC	FACE OF CURB	SS
FF FG FH	FINISHED FLOOR FINISHED GRADE FIRE HYDRANT	SS SSCO SSMH ST.
FL	FLOW LINE	STA
FS	FINISHED SURFACE	STD
G	GAS	STRUCT
GA GB HDPE	GAGE OR GAUGE GRADE BREAK HIGH DENSITY CORRUGATED POLYETHYLENE PIPE	T TC TOW TEMP
HORIZ	HORIZONTAL	TP
HI PT	HIGH POINT	TW/FG
H&T	HUB & TACK	TYP
ID	INSIDE DIAMETER	VC
INV	INVERT ELEVATION	VCP
JB	JUNCTION BOX	VERT
JT JP L LNDG	JOINT TRENCH JOINT UTILITY POLE LENGTH LANDING	W/ W, WL WM
		WWF


# LINEAR FEET MAX



PRELIMINARY GRADING & DRAINAGE

1 OF 5 SHEETS





## **PURPOSE:**

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS NECESSARY. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. LEA & BRAZE ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD CONDITIONS CHANGE.

## **EROSION CONTROL NOTES:**

- 1. IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
- 2. THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL. THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT
- 3. OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
- 4. SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT-LADEN RUNOFF TO ANY STORM DRAINAGE SYSTEM. INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
- 6. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
- 7. CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
- 8. ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 15TH.
- 9. EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS LONGER.
- 10. IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
- 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
- 12. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY LOCAL JURISDICTION'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
- 13. MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SURFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
- 14. EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH THRU APRIL 15TH.
- 15. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM OCTOBER X THROUGH APRIL X. WHICHEVER IS GREATER.
- 16. PLANS SHALL BE DESIGNED TO MEET C3 REQUIREMENTS OF THE MUNICIPAL STORMWATER REGIONAL PERMIT("MRP") NPDES PERMIT CAS 612008.
- 17. THE CONTRACTOR TO NPDES (NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM) BEST MANAGEMENT PRACTICES (BMP) FOR SEDIMENTATION PREVENTION AND EROSION CONTROL TO PREVENT DELETERIOUS MATERIALS OR POLLUTANTS FROM ENTERING THE TOWN OR COUNTY STORM DRAIN SYSTEMS.
- 18. THE CONTRACTOR MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE INCEPTION OF ANY WORK ONSITE AND MAINTAIN THE MEASURES UNTIL THE COMPLETION OF ALL LANDSCAPING.
- 19. THE CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN DUST FREE AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE TOWN INSPECTOR. THE ADJACENT STREET SHALL AT ALL TIMES BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. THE CONTRACTOR BE RESPONSIBLE FOR ANY CLEAN UP ON ADJACENT STREETS AFFECTED BY THE BY THEIR CONSTRUCTION. METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BUILDING MATERIALS WITHIN THE TOWN RIGHT-OF-WAY.
- 20. SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE PRIOR TO THE INSPECTION OF ANY WORK ONSITE AND MAINTAIN IT FOR THE DURATION OF THE CONSTRUCTION PROCESS SO AS TO NOT INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC RIGHT-OF-WAY UNTIL THE COMPLETION OF ALL LANDSCAPING.
- 21. THE CONTRACTOR SHALL PROTECT DOWN SLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH ROCK FILLED SAND BAGS, TEMPORARY SWALES, SILT FENCES, AND EARTH PERMS IN CONJUNCTION OF ALL LANDSCAPING.
- 22. STOCKPILED MATERIALS SHALL BE COVERED WITH VISQUEEN OR A TARPAULIN UNTIL THE MATERIAL IS REMOVED FROM THE SITE. ANY REMAINING BARE SOIL THAT EXISTS AFTER THE STOCKPILE HAS BEEN REMOVED SHALL BE COVERED UNTIL A NATURAL GROUND COVER IS ESTABLISHED OR IT IS SEEDED OR PLANTED TO PROVIDE GROUND COVER PRIOR TO THE FALL RAINY SEASON.
- 23. EXCESS OR WASTE CONCRETE MUST NOT BE WASHED INTO THE PUBLIC RIGHT-OF-WAYOR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE.
- 24. TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION AND DISPERSAL BY WIND

## EROSION CONTROL NOTES CONTINUED:

- 24. FUELS, OILS, SOLVENTS AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE THE SOIL AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MUST NOT BE WASHED INTO THE DRAINAGE SYSTEM.
- 25. DUST CONTROL SHALL BE DONE BY WATERING AND AS OFTEN AS REQUIRED BY THE TOWN INSPECTOR.
- 26. SILT FENCE(S) AND/OR FIBER ROLL(S) SHALL BE INSTALLED PRIOR TO SEPTEMBER 15TH AND SHALL REMAIN IN PLACE UNTIL THE LANDSCAPING GROUND COVER IS INSTALLED. CONTRACTOR SHALL CONTINUOUSLY MONITOR THESE MEASURES. FOLLOWING AND DURING ALL RAIN EVENTS. TO PUBLIC OWNED FACILITIES.

## **EROSION CONTROL MEASURES:**

- 1. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 15TH TO APRIL 15. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 15TH OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
- 2. SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
- 3. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
- 4. ALL EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDED. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15. THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE-STEP APPLICATION OF 1) SEED, MULCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYDROSEEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER INFORMATION.
- 5. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
- 6. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF LEA & BRAZE ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY LEA & BRAZE ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
- 7. THE EROSION CONTROL MEASURES SHALL CONFORM TO THE LOCAL JURISDICTION'S STANDARDS AND THE APPROVAL OF THE LOCAL JURISDICTION'S ENGINEERING DEPARTMENT.
- 8. STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWN SLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY END BUTTED. CONTRACTOR SHALL REFER TO MANUFACTURES SPECIFICATIONS FOR PLACEMENT AND INSTALLATION INSTRUCTIONS.

## **REFERENCES:**


- 1. CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
- 2. CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

## **PERIODIC MAINTENANCE:**


- 1. MAINTENANCE IS TO BE PERFORMED AS FOLLOWS: A. DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE
- B. SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
- C. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
- D. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1' FOOT.
- E. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- F. RILLS AND GULLIES MUST BE REPAIRED.
- SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- 3. STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.
- 4. SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
- 5. CONSTRUCTION ENTRANCE SHALL BE REGRAVELED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
- 6. ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION


REPAIRED AT THE END OF EACH WORKING DAY.

2. GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER



PRELIMINARY GRADING & DRAINAGE






STABILIZED CONSTRUCTION SITE ACCESS SHALL BE CONSTRUCTED OF 3" TO 4" WASHED, FRACTURED


MATERIAL SHALL BE PLACED TO A LENGTH OF ENTRANCE SHALL BE A

WIDTH SHALL BE A MIN. OF 15' OR GREATER IF NECESSARY TO COVER ALL VEHICULAR INGRESS AND EGRESS. PROVIDE AMPLE TURNING

THE ENTRANCE SHALL BE KEPT IN GOOD CONDITION BY OCCASIONAL TOP DRESSING WITH MATERIAL AS

PERIODIC TOP DRESSING SHALL BE DONE AS NEEDED.





## FRONT YARD PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QTY
TREES				
ACE AUT	Acer rubrum 'Autumn Blaze' - std	Autumn Blaze Maple	24" box	1
	Hibiscus rosa-sinensis 'Butterfly' - std.	Yellow Tropical Hibiscus	15 gal	4
LAG NAT	Lagerstroemia 'Natchez' - std.	White Crape Myrtle	24" box	12
SHRUBS				
LIG TEX	Ligustrum japonicum 'Texanum'	Japanese Privet	5 gal	34
LOR SPR	Loropetalum chinense 'Spring Snow'	Green Chinese Fringe Flower	5 gal	36
MYR AFR	Myrsine africana	African Boxwood	5 gal	6
MYR COV	Myrtus communis 'Compacta Variegata'	Variegated Compact Myrtle	5 gal	35
OLE LIT	Olea europaea 'Little Ollie'	Olive	5 gal	8
RIB ICE	Ribes sanguineum 'White Icicle'	White Winter Current	5 gal	1
PERENNIALS	<u>}</u>			
ANI HYB	Anigozanthos hybridus-Gold	Kangaroo Paw	1 gal	8
GROUNDCO	/ER			
CEA VAL	Ceanothus maritimus 'Valley Violet'	Valley Violet Ceanothus	1 gal	13
COT MIC	Cotoneaster microphyllus	Rockspray Cotoneaster	1 gal	19
GRASSES				
CAR DIV	Carex divulsa	Berkeley Sedge	1 gal	123
LOM BRE	Lomandra longifolia 'Breeze'	Dwarf Mat Rush	1 gal	55

Y	RATE OF GROWTH
	Madium
	Medium
	Fast
	Fast
	Fast
	Medium
	Slow
	Slow
	Slow
	Medium
	Feet
	Fast
	Slow
	Medium
3	Fast
,	Fast
	1 431

	SCAPE SC	REENING F	PLANT	LIST	I
SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	ΟΤΥ	RΔT

SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QTY	RATE OF GROWTH
TREES					
POD GRT	Podocarpus gracilior	Fern Pine	15 gal	3	Medium
SHRUBS					
PIT TEN	Pittosporum tenuifolium	•	15 gal	66	Fast
POD GRS	Podocarpus gracilior	Fern Pine	15 gal	24	Medium



POD GRT : PODOCARPUS GRACILIOR (TREE FORM) SIZE AT PLANTING : 6'-7' T x 3' W SIZE AT ~15 YEARS : 14' T x 7' W





POD GRS : PODOCARPUS GRACILIOR (SHRUB FORM) SIZE AT PLANTING : 5'-6' T x 2' W SIZE AT ~15 YEARS : 12' T x 6' W




PIT TEN : PITTOSPORUM TENUIFOLIUM SIZE AT PLANTING : 5'-6' T x 2' W SIZE AT ~15 YEARS : 20' T x 6' W









## **IRRIGATION SCHEDULE**

FOR THE EFFICIENT USE OF WATER, ALL IRRIGATION SCHEDULES SHALL BE DEVELOPED, MANAGED, AND EVALUATED TO UTILIZE THE MINIMUM AMOUNT OF WATER REQUIRED TO MAINTAIN PLANT HEALTH. IRRIGATION SCHEDULES SHALL MEET THE FOLLOWING CRITERIA:

- 1. IRRIGATION SCHEDULING SHALL BE REGULATED BY AUTOMATIC IRRIGATION CONTROLLERS.
- 2. OVERHEAD IRRIGATION SHALL BE SCHEDULED BETWEEN 8:00 P.M. AND 10:00 A.M. UNLESS WEATHER CONDITIONS PREVENT IT. IF ALLOWABLE HOURS OF IRRIGATION DIFFER FROM THE LOCAL WATER PURVEYOR, THE STRICTER OF THE TWO SHALL APPLY. OPERATION OF THE IRRIGATION SYSTEM OUTSIDE THE NORMAL WATERING WINDOW IS ALLOWED FOR AUDITING AND SYSTEM MAINTENANCE.
- 3. FOR IMPLEMENTATION OF THE IRRIGATION SCHEDULE, PARTICULAR ATTENTION MUST BE PAID TO IRRIGATION RUN TIMES, EMISSION DEVICE, FLOW RATE, AND CURRENT REFERENCE EVAPOTRANSPIRATION, SO THAT APPLIED WATER MEETS THE ESTIMATED TOTAL WATER USE (ETWU). TOTAL ANNUAL APPLIED WATER SHALL BE LESS THAN OR EQUAL TO MAXIMUM APPLIED WATER ALLOWANCE (MAWA). ACTUAL IRRIGATION SCHEDULES SHALL BE REGULATED BY AUTOMATIC IRRIGATION CONTROLLERS USING CURRENT REFERENCE EVAPOTRANSPIRATION DATA (E.G., CIMIS) OR SOIL MOISTURE SENSOR DATA.
- 4. PARAMETERS USED TO SET THE AUTOMATIC CONTROLLER SHALL BE DEVELOPED AND SUBMITTED FOR EACH OF THE FOLLOWING: (A) THE PLANT ESTABLISHMENT PERIOD. (B) THE ESTABLISHED LANDSCAPE.
  - (C) TEMPORARILY IRRIGATED AREAS.
- 5. EACH IRRIGATION SCHEDULE SHALL CONSIDER FOR EACH STATION ALL OF THE FOLLOWING THAT APPLY:

(A) IRRIGATION INTERVAL (DAYS BETWEEN IRRIGATION) (B) IRRIGATION RUN TIMES (HOURS OR MINUTES PER IRRIGATION EVENT TO AVOID RUNOFF (C) NUMBER OF CYCLE STARTS REQUIRED FRO EACH IRRIGATION EVENT TO AVOID RUNOFF (D) AMOUNT OF APPLIED WATER SCHEDULED TO BE APPLIED ON A MONTHLY BASIS (E) APPLICATION RATE SETTING

- (F) ROOT DEPTH SETTING (G) PLANT TYPE SETTING
- (H) SOIL TYPE
- (I) SLOPE FACTOR SETTING

(J) SHADE FACTOR SETTING (K) IRRIGATION UNIFORMITY OR EFFICIENCY SETTING

- 6. THE CONTRACTOR SHALL SET UP SOAK CYCLES WITH MULTIPLE START TIMES WHICH WILL ELIMINATE POOLING AND RUN OFF. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MANAGE LANDSCAPE SO AS TO NOT EXCEED THE ESTIMATED ETWU.
- 7. FOR IRRIGATION ZONE SCHEDULING, REFER TO MWELO CALCULATIONS FOR VALVE ZONE ETWU.
- 8. APPROXIMATE IRRIGATION DAYS (52 TOTAL) JANUARY (1), FEBRUARY (2), MARCH (4), APRIL (5), MAY (7), JUNE (8), JULY (8), AUGUST (7), SEPTEMBER (5), OCTOBER (3), NOVEMBER (3), DECEMBER (1)

# **GENERAL IRRIGATION NOTES**

### 1. THESE IRRIGATION PLANS ARE DIAGRAMMATIC ONLY. ALL PIPING, VALVES, ETC. SHALL BE LOCATED IN PLANTING AREAS EVEN THOUGH THEY MAY APPEAR IN PAVING AREAS. 2. ALL IRRIGATION COMPONENTS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS AND PER LOCAL CODES. 3. THE CONTRACTOR SHALL NOTIFY ALL LOCAL JURISDICTIONS FOR INSPECTION AND TESTING OF INSTALLED BACK FLOW PREVENTION DEVICE. 4. THE CONTRACTOR SHALL VERIFY ADEQUATE WATER PRESSURE PRIOR TO CONSTRUCTION. NOTIFY THE LANDSCAPE ARCHITECT IF MEASURED PRESSURE IS MORE THAN 85 P.S.I. OR LESS THAN 50 P.S.I. 5. PRIOR TO TRENCHING, CONTACT USA NORTH 811 ONLINE AT WWW.USANORTH811.ORG. 6. WHERE IT IS NECESSARY TO EXCAVATE AROUND (E) TREES, THE CONTRACTOR SHALL USE ALL POSSIBLE CARE TO AVOID INJURY TO TREE AND TREE ROOTS. IN AREAS WHERE 2 INCHES AND LARGER ROOTS OCCUR, EXCAVATION SHALL BE DONE BY HAND. ROOTS 2 INCHES AND LARGER IN DIAMETER SHALL BE WRAPPED IN A PLASTIC BAG AND SECURED WITH A RUBBER BAND. TRENCHES ADJACENT TO TREES SHOULD BE CLOSED WITHIN TWENTY FOUR (24) HOURS; WHERE THIS IS NOT POSSIBLE, THE SIDE OF THE TRENCH ADJACENT TO THE TREE SHALL BE KEPT SHADED WITH BURLAP OR CANVAS. 7. THE ELECTRICAL CONTRACTOR SHALL SUPPLY 120 VOLT SERVICE TO THE CONTROLLER LOCATION AND THE LANDSCAPE CONTRACTOR SHALL MAKE THE FINAL CONNECTION FROM THE STUB-OUT TO THE CONTROLLER. IRRIGATION CONTROL WIRE SHALL BE #14 U.L. APPROVED FOR DIRECT BURIAL. THE COMMON WIRE SHALL BE #12. 8. ALL IRRIGATION VALVE BOXES SHALL BE BLACK PLASTIC WITH NON-HINGED COVERS. INSTALL VALVE BOXES IN SHRUB AREAS AND A MINIMUM OF 12 INCHES FROM AND PERPENDICULAR TO WALK, CURB, ETC. OR LANDSCAPE FEATURE. AT MULTIPLE VALVE BOX GROUPS, EACH BOX SHALL BE AN EQUAL DISTANCE FROM THE WALK, CURB, ETC., AND EACH BOX SHALL BE A MINIMUM OF 12 INCHES APART. SHORT SIDE OF VALVE BOX SHALL BE PARALLEL TO WALK, CURB, ETC. 9. SPLICING OF 24 VOLT WIRES WILL NOT BE PERMITTED EXCEPT IN VALVE BOXES. LEAVE A 36 INCH COIL OF ACCESS WIRE AT EACH SPLICE AND 100 FEET ON CENTER ALONG WIRE RUN. TAPE WIRE IN BUNDLES 10 FEET ON CENTER. NO TAPING PERMITTED INSIDE SLEEVES. 10. ALL SPRINKLER HEADS SHALL BE PERPENDICULAR TO FINISH GRADE. INSTALL CHECK VALVES IN AREAS OF VARIABLE PRESSURE AND/OR STEEP SLOPES TO PREVENT LOW HEAD DRAINAGE. 11. THE CONTRACTOR SHALL FLUSH ALL IRRIGATION LINES AND ADJUST ALL SPRINKLER HEADS FOR OPTIMUM PERFORMANCE AND TO PREVENT OVER SPRAY ONTO WALKS, ROADWAYS AND BUILDINGS.

- 12. INSTALL TREE BUBBLERS ON UPHILL SIDE OF TRUNK AND ADJUST FOR DEEP ROOT WATERING.
- 13. THE CONTRACTOR SHALL PROVIDE OWNER WITH A COMPLETE AS-BUILT DRAWING OF THE IRRIGATION SYSTEM PRIOR TO RECEIPT OF FINAL PAYMENT.

# LANDSCAPE & IRRIGATION MAINTENANCE SCHEDULE

THE LANDSCAPE SHALL BE MAINTAINED TO INSURE WATER EFFICIENCY PER STATE CODE. THE LANDSCAPE MAINTENANCE CONTRACTOR SHALL ADJUST THE IRRIGATION SYSTEM TO APPLY WATER IN ACCORDANCE WITH PLANT REQUIREMENTS BASED ON WEATHER, SOIL, AND SITE CONDITIONS. THE IRRIGATION CONTROLLER SHALL BE PROGRAMMED TO MINIMIZE RUNOFF AND TO UTILIZE CYCLE SOAK WHEN APPLICABLE. A REGULAR MAINTENANCE SCHEDULE SHALL INCLUDE:

- 1. ROUTINE INSPECTIONS INCLUDING AUDITING, ADJUSTING AND REPAIRING IRRIGATION SYSTEM AND COMPONENTS.
- 2. AERATING AND DETHATCHING TURF AREAS.
- 3. TOP DRESSING WITH COMPOST AND REPLENISHING MULCH.
- 4. FERTILIZING, PRUNING AND WEEDING IN ALL LANDSCAPE AREAS.
- 5. REMOVING OBSTRUCTIONS TO EMISSION DEVICES.
- 6. OPERATING THE IRRIGATION SYSTEM OUTSIDE THE NORMAL WATERING WINDOW FOR AUDITING AND SYSTEM MAINTENANCE, WHICH IS ALLOWED.
- 7. REPAIRING IRRIGATION EQUIPMENT SHALL BE DONE WITH ORIGINALLY SPECIFIED MATERIALS.
- 8. MONITORING ALL TURF AREAS FOR ADEQUATE IRRIGATION. FREQUENCY AND DURATION WILL BE DEPENDENT ON LOCAL WEATHER AND SITE CONDITIONS. DEEP ROOT WATERING, LONGER IRRIGATION TIMES WITHOUT RUN OFF, AND THE USE OF CYCLE SOAK IS PREFERRED TO ENCOURAGE DEEP ROOT GROWTH.
- 9. MAINTAINING ALL BACKFLOW PREVENTION DEVICES AS PER LOCAL CITY OR COUNTY CODES.

## IRRIGATION I FGEND


SYMBOL	DESCRIPTION	MODEL	FLOW RATE/APP RATE
•	HUNTER DRIP ZONE VALVE KIT (REMOTE CONTROL VALVE, WYE FILTER AND PRESSURE REGULATOR), OR APPROVED EQUAL. INSTALL BALL VALVE UPSTREAM OF REMOTE CONTROL VALVE	ICZ-101-LF-25	
	HUNTER REMOTE CONTROL VALVE, OR APPROVED EQUAL (LINE SIZE)	ICV-G	
0	COMPRESSION FITTING- RIGID PIPE/POLY PIPE POINT OF DRIP CONNECTION ABOVE GRADE		
M	NIBCO GATE VALVE (LINE SIZE)		
W	WATER METER		
♦	SUPERIOR 1 $\frac{1}{2}$ " MASTER CONTROL VALVE, OR APPROVED EQUAL	3300150	
BF	WILKINS REDUCED PRESSURE BACKFLOW PREVENTER, OR APRROVED EQUAL	975XL2-1 <sup>1</sup> / <sub>2</sub> "	
FC	HUNTER PVC FLOW SENSOR	HFS-FCT-(LINE SIZE)	
C 18	HUNTER I-CORE CONTROLLER (36 STATION) WALL MOUNT W/ REMOTE, OR APPROVED EQUAL.	IC-3600-PL-ROAM-KIT	
63	HUNTER SOLAR SYNC WIRELESS WEATHER SENSOR, OR APPROVED EQUAL	WSS-SEN	
POC	POINT OF CONNECTION		
$\oplus$	ARROWHEAD HOSE BIB W/ INTERNAL VACUUM BREAKER	261	
	LATERAL LINE: 1120- SCHEDULE 40 PVC. SOLVENT WELD PIPE W/ SCHEDULE 40 SOLVENT WELD FITTINGS. (12" COVER)		
	MAINLINE: 1120- SCHEDULE 40 PVC. SOLVENT WELD PIPE W/ SCHEDULE 40 SOLVENT WELD FITTINGS. (18" COVER)		
	4" PVC SLEEVE (24" COVER)		
	—— GALLONS PER MINUTE		
<b>†</b>	VALVE SIZE		

PLAN."

SIGNED:


MAMAN INN

"I HAVE COMPLIED WITH THE CRITERIA OF THE MODEL WATER EFFICIENT LANDSCAPE ORDINANCE ANDAPPLIED THEM ACCORDINGLY FOR THE EFFICIENT USE OF WATER IN THE IRRIGATION DESIGN





6




LATERAL TEE OR ELL

SWING JOINT: HUNTER 'PRO-FLEX' TUBING, HSBE-050 ELBOWS (2), & MARLEX STREET ELBOW (1)

MODEL PROS-06-CV SPRAY HEAD


RECLAIMED CAP, MODEL #45852X


FLUSH VALVE - DRIP LINE





SCALE: NTS






- HUNTER DRIP EMITTER


20\*



## POINT SOURCE DRIP EMITTER DETAIL SCALE: NTS





\* DISTRIBUTE EMITTERS ON 2 DRIP RINGS






4







# VALVE BOX INSTALLATION DETAIL

SCALE: NTS

5

