

FIRE DEPARTMENT NOTES:

- REVIEW OF THIS DEVELOPMENTAL PROPOSAL IS LIMITED TO ACCEPTABILITY OF SITE ACCESS AND WATER SUPPLY AS THEY PERTAIN TO FIRE DEPARTMENT OPERATIONS, AND SHALL NOT BE CONSTRUED AS A SUBSTITUTE FOR FORMAL PLAN REVIEW TO DETERMINE COMPLIANCE WITH ADOPTED MODEL CODES. PRIOR TO PERFORMING ANY WORK THE APPLICANT SHALL MAKE APPLICATION TO AND RECEIVE FROM THE BUILDING DEPARTMENT ALL APPLICABLE CONSTRUCTION PERMITS.
- AN AUTOMATIC RESIDENTIAL FIRE SPRINKLER SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH NATIONAL FIRE PROTECTION ASSOCIATION'S (NFPA) STANDARD 13D IN ALL NEW ONE AND TWO-FAMILY DWELLINGS AND IN EXISTING DWELLINGS, WHEN ADDITIONS ARE MADE THAT INCREASE THE BUILDING AREA TO MORE THAN THE ALLOWABLE FIRE-FLOW APPENDIX TABLE B101L, OR ADDITIONS EXCEEDS FIFTY (50) PERCENT (INCLUSIVE OF GARAGE CONVERSIONS) OF THE EXISTING LIVING AREA (EXISTING SQUARE FOOT CALCULATIONS SHALL NOT INCLUDE EXISTING BASEMENT) WHEN AUTOMATIC FIRE SPRINKLER SYSTEMS ARE REQUIRED BY THIS SECTION. ALL ASSOCIATED GARAGES SHALL BE INCLUDED. TEAR-DOWNS AND/OR ADDITIONS OVER FIFTY (50) PERCENT SHALL BE TREATED AS A NEW STRUCTURE REGARDING INSTALLATION OF FIRE SPRINKLER SYSTEMS. THE OBLIGATION TO PROVIDE COMPLIANCE WITH THESE FIRE SPRINKLER REGULATIONS MAY NOT BE EVADED BY PERFORMING A SERIES OF SMALL ADDITIONS UNDERTAKEN OVER A THREE-YEAR PERIOD. THE PERMIT ISSUANCE DATE OF ANY ADDITIONS WHERE THESE REGULATIONS WERE IN EFFECT SHALL BE USED FOR DETERMINING COMPLIANCE. NOTE: THE OWNER(S), OCCUPANT(S) AND ANY CONTRACTOR(S) OR SUBCONTRACTOR(S) ARE RESPONSIBLE FOR CONSULTING WITH THE WATER PURVEYOR OF RECORD IN ORDER TO DETERMINE IF ANY MODIFICATION OR UPGRADE OF THE EXISTING WATER SERVICE IS REQUIRED. A STATE OF CALIFORNIA LICENSED (C-4) FIRE PROTECTION CONTRACTOR SHALL SUBMIT PLANS, CALCULATIONS, A COMPLETED PERMIT APPLICATION AND APPROPRIATE FEES TO THIS DEPARTMENT FOR REVIEW AND APPROVAL PRIOR TO BEGINNING THEIR WORK. CRC SEC. 313.2 AS ADOPTED AND AMENDED BY LANC.
- POTABLE WATER SUPPLIES SHALL BE PROTECTED FROM CONTAMINATION CAUSED BY FIRE PROTECTION WATER SUPPLIES. IT IS THE RESPONSIBILITY OF THE APPLICANT AND ANY CONTRACTORS AND SUBCONTRACTORS TO CONTACT THE WATER PURVEYOR SUPPLYING THE SITE OF SUCH PROJECT, AND TO COMPLY WITH THE REQUIREMENTS OF THAT PURVEYOR. SUCH REQUIREMENTS SHALL BE INCORPORATED INTO THE DESIGN OF ANY WATER-BASED FIRE PROTECTION SYSTEM(S), AND/OR FIRE SUPPRESSION WATER SUPPLY SYSTEMS OR STORAGE CONTAINERS THAT MAY BE PHYSICALLY CONNECTED IN ANY MANNER TO AN APPLIANCE CAPABLE OF CAUSING CONTAMINATION OF THE POTABLE WATER SUPPLY OF THE PURVEYOR OF RECORD. FINAL APPROVAL OF THE SYSTEMS UNDER CONSIDERATION WILL NOT BE GRANTED BY THIS OFFICE UNTIL COMPLIANCE WITH THE REQUIREMENTS OF THE WATER PURVEYOR OF RECORD ARE DOCUMENTED BY THAT PURVEYOR AS HAVING BEEN MET BY THE APPLICANT(S). 2010 CFC SEC. 403.3.5 AND HEALTH AND SAFETY CODE 1914.1
- ALL CONSTRUCTION SITES MUST COMPLY WITH APPLICABLE PROVISIONS OF THE CFC CHAPTER 33 AND OUR STANDARD DETAIL AND SPECIFICATIONS SI-1. PROVIDE APPROPRIATE NOTATIONS ON SUBSEQUENT PLAN SUBMITTALS TO THE PROJECT. CFC CHAPTER 33.
- NEW AND EXISTING BUILDINGS SHALL HAVE APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR APPROVED BUILDING IDENTIFICATION PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY. THESE NUMBERS SHALL CONTRAST WITH THEIR BACKGROUND. ADDRESS NUMBERS SHALL BE ARABIC NUMBERS OR ALPHABETICAL LETTERS. NUMBERS SHALL BE A MINIMUM OF 4 INCHES (101.4 MM) HIGH WITH A MINIMUM STROKE WIDTH OF 0.5 INCH (12.7 MM). WHERE ACCESS IS BY MEANS OF A PRIVATE ROAD AND THE BUILDING CANNOT BE VIEWED FROM THE PUBLIC WAY, A MONUMENT, POLE OR OTHER SIGN OR MEANS SHALL BE USED TO IDENTIFY THE STRUCTURE. CFC SEC/ 505.1

ZONING COMPLIANCE			
	EXISTING	PROPOSED	ALLOWED/REQ'D
LOT COVERAGE (AND AREA COVERED BY ALL STRUCTURES THAT ARE OVER 8' HIGH)	4,024 S.F. 14.6%	6,025 S.F. 21.8%	9,087 S.F. 30.0%
FLOOR AREA: MEASURED TO THE OUTSIDE SURFACES OF EXTERIOR WALLS	1st FLR. 3,343 S.F. 2nd FLR. 2,010 S.F. TOTAL 5,353 S.F. 19.4%	3,584 S.F. 1,627 S.F. 5,211 S.F. 18.9%	6,312 S.F. 22.9%
ADU	598 S.F.	1,100 S.F.	1,200 S.F.
SETBACKS:			
FRONT	70.3 FT.	51 FT.	25 FT.
REAR	58.2 FT.	39.8 FT.	25 FT.
RIGHT SIDE (1ST/2ND)	26.4/26.4 FT.	22.3/25.2 FT.	10/17.5 FT.
LEFT SIDE (1ST/2ND)	45.7/53.4 FT.	28.6/32.4 FT.	10/17.5 FT.
HEIGHT:	23.3 FT.	25.4 FT.	27 FT.
SQUARE FOOTAGE BREAKDOWN			
	EXISTING	CHANGE IN	TOTAL PROPOSED
HABITABLE LIVING AREA: INCLUDES HABITABLE BASEMENT AREAS	5,993 S.F.	3,264 S.F.	9,257 S.F.
NON-HABITABLE AREA: DOES NOT INCLUDE COVERED PORCHES OR DECK/STAIRWAYS	1,008 S.F.	-370 S.F.	638 S.F.
LOT CALCULATIONS			
NET LOT AREA:			27,622 S.F.
FRONT YARD HARDSCAPE AREA: HARDSCAPE AREA IN THE FRONT YARD SETBACK SHALL NOT EXCEED 50%		1,259 S.F.	37.7%
LANDSCAPE BREAKDOWN:			17,254 S.F.
			0 S.F.
			10,368 S.F.



RENDERED 3D IMAGE

PROJECT INFO

OWNER: ALAN & LAURA GREBENE
12 VIEW STREET
LOS ALTOS, CA 94022

JOB ADDRESS: 12 VIEW STREET
LOS ALTOS, CA 94022

BUILDING OCCUPANCY GROUP(S): R-3/U

TYPE(S) OF CONSTRUCTION: X-B

RISK CATEGORY: II

A.P.N.: 147-34-025

ZONING: RI-10

ARCHITECT: RH ASSOCIATES, ARCHITECTS
11010 COMBIE RD, STE 210
AUBURN, CA 95602
CONTACT: J. STEVE COLLOM
(530) 248-3055
steve.colom@gmail.com

CIVIL ENGINEER: NNR ENGINEERING
535 WIEYBRIDGE DRIVE
SAN JOSE, CA 95123
CONTACT: NADIM RAFOUL
(408) 348-7818
nnrengineering@yahoo.com

ARBORIST: ARBORWELL
2331 AMERICAN AVE
HAYWARD, CA 94545
CONTACT: SAMUEL OAKLEY
(888) 941-8132
soakley@arborwell.com

GEOTECHNICAL ENGINEER: SILICON VALLEY SOIL ENGINEERING
2941 ZANKER ROAD, SUITE 350
SAN JOSE, CA 95131
CONTACT: SEAN DEIVERT
(408) 324-1400
sdeivert@siliconvalleysoil.com


LANDSCAPE DESIGN: KAREN AITKEN & ASSOCIATES
8242 RANCHO REAL
GILROY, CA 95020
CONTACT: KAREN AITKEN
(408) 842-0245
AitkenAssociates@gmail.com

AREA SCHEDULE

LOT AREA	27,422 S.F.
LIVABLE AREA	
BASEMENT	3,584 S.F.
MAIN FLOOR	2,944 S.F.
UPPER FLOOR	1,627 S.F.
	TOTAL 8,157 S.F.
ADU	1,100 S.F.
TOTAL LIVABLE W/ ADU	9,257 S.F.
GARAGE	438 S.F.
COVID ENTRY	93 S.F.
COVID PORCH	45 S.F.
REAR COVID TERRACE	438 S.F.
A.D.U. COVID TERRACE	432 S.F.
CHIMNEYS	23 S.F.
POOL EQUIP	90 S.F.
COVERAGE	
ALLOWED (30%+800)	9,087 S.F.
EXISTING	4,024 S.F.
PROPOSED	4,025 S.F.
FLOOR AREA	
ALLOWED (3,850+1,442+800)	4,312 S.F.
EXISTING	5,353 S.F.
PROPOSED	4,311 S.F.

SCOPE OF WORK:

THE CONSTRUCTION OF A TWO-STORY, 4514 SQUARE FOOT HOUSE WITH ATTACHED 438 SQUARE FOOT GARAGE OVER A 3584 SQUARE FOOT BASEMENT AND A DETACHED 1100 ACCESSORY DWELLING UNIT (A.D.U.) UNDER SEPARATE PERMIT.



VICINITY MAP
NO SCALE NORTH



2 SITE SECTION
1/8" = 1'-0"
0 2 4 12 20



3 SITE SECTION
1/8" = 1'-0"
0 2 4 12 20

ASSOCIATES ARCHITECTS
11010 COMBIE RD, STE. 210
AUBURN, CA 95602
530-268-3055
J. STEVE COLLOM
rhassociates.com
rhassoc@rhaglobal.net

REGISTERED ARCHITECT
STEVE COLLOM
No. C 11982
Exp. 10-21
STATE OF CALIFORNIA

A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREBENE
LOS ALTOS, CALIFORNIA
T2 VIEW STREET

drawings
COVER PAGE


revisions

project number
2559

date
JULY 2, 2021


sheet number
A1

ITEM #	SIZE DBH	DESCRIPTION	REMOVE
1	36"	COAST LIVE OAK	NO
2	36"	COAST LIVE OAK	NO
3	12"	CHINESE PISTACHE	NO
4	6"	CHINESE PISTACHE	NO
5	12"	COAST LIVE OAK	NO
6	6"	AFRICAN SUIVAC	NO
7	8"	AFRICAN SUIVAC	NO
8	8"	AFRICAN SUIVAC	YES
9	8"	CARROTWOOD	YES
10	36"	COAST LIVE OAK	NO
11	6"	JAPANESE MAPLE	YES
12	8"	STRAWBERRY MADRONE	NO
13	8"	STRAWBERRY MADRONE	NO
14	6"	STRAWBERRY MADRONE	NO
15	6"	CITRUS	YES
16	10"	CHINESE PISTACHE	NO
17	10"	CHINESE PISTACHE	NO
18	10"	CHINESE PISTACHE	NO
19	8"	CHINESE PISTACHE	NO
20	10"	CHINESE PISTACHE	NO
21	10"	CHINESE PISTACHE	NO
22	12"	MAYTEN	NO
23	10"	MAYTEN	NO
24	10"	MAYTEN	NO
25	10"	MAYTEN	NO



A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
 LOS ALTOS, CALIFORNIA
T2 VIEW STREET

drawings	SITE PLAN
revisions	
project number	2559
date	JULY 2, 2021
sheet number	A1a



MAIN FLOOR

12	24.17	x	42.17	=	1023.59
13	18.82	x	15.47	=	291.91
14	1.50	x	11.50	=	17.25
15	34.00	x	29.33	=	1058.00
16	21.00	x	3.41	=	71.71
17	5.50	x	19.52	=	107.31
18	13.33	x	18.92	=	252.01
19	3.42	x	3.15	=	10.78
20	3.15	x	1.17	=	3.68
21	NOT USED			=	0.00
22	3.42	x	3.42	=	11.79
TOTAL				=	2444

GARAGE

23	20.53	x	11.83	=	242.48
24	20.11	x	4.50	=	90.49
25	20.41	x	4.33	=	88.78
26	1.50	x	18.50	=	27.75
TOTAL				=	639

COVID ENTRY

27	11.82	x	3.41	=	40.38
28	12.33	x	1.00	=	12.33
TOTAL				=	52.71

COVID PORCH

29	13.33	x	4.41	=	58.78
30	1.00	x	3.00	=	3.00
TOTAL				=	61.78

COVID PORCH


31	24.17	x	21.00	=	507.57
32	18.00	x	4.15	=	74.65
33	1.50	x	1.17	=	1.75
TOTAL				=	583.97

CHIMNEYS

34	2.00	x	6.00	=	12.00
35	2.00	x	5.61	=	11.22
TOTAL				=	23.22

UPPER FLOOR

36	13.00	x	15.50	=	201.50
37	15.33	x	15.50	=	237.62
38	8.33	x	4.50	=	37.49
39	11.33	x	10.17	=	115.25
40	5.00	x	12.17	=	60.85
41	18.00	x	11.17	=	201.06
42	11.00	x	11.50	=	126.50
43	11.50	x	11.50	=	132.25
44	0.50	x	1.50	=	0.75
45	11.00	x	18.33	=	201.63
46	4.82	x	16.33	=	78.81
47	8.41	x	4.00	=	33.64
48	11.33	x	1.00	=	11.33
49	11.33	x	1.00	=	11.33
50	IRREGULAR			=	5.00
TOTAL				=	1421



FOR 1/4 SCALE PLAN
 SEE SHEET A4


FOR 1/4 SCALE PLAN
 SEE SHEET A3

1 AREA DIAGRAMS
 A2 1/8" = 1'-0"


2 1/8 SCALE KEY PLAN
 A2 1/8" = 1'-0"

NORTH

NORTH




ASSOCIATES ARCHITECTS
 11010 combe rd. ste. 210
 AUBURN, CA 95602
530-268-3055
 J. STEVE COLLOM
 rhaarchitects.com
 rhassoo@abglobal.net




A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
 LOS ALTOS, CALIFORNIA
T2 VIEW STREET

drawings	BASEMENT
revisions	
project number	2559
date	JULY 2, 2021
sheet number	A3


1 BASEMENT FLOOR PLAN
 A3 1/4" = 1'-0" 0 1 3 6 10 NORTH




MAIN FLOOR PLAN - PARTIAL
 1/4" = 1'-0"



15-5-2021 5:00 AM



ASSOCIATES
ARCHITECTS
11010 combe rd. ste. 210
AUBURN, CA 95602
530-268-3055
J. STEVE COLLOM
rhaarchitects.com
rhaassoc@abglobal.net



A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
LOS ALTOS, CALIFORNIA
T2 VIEW STREET

drawings
MAIN FLOOR


revisions

project number
2559

date
JULY 2, 2021

sheet number


A5




1 MAIN FLOOR PLAN - PARTIAL
A5 1/4" = 1'-0"




NORTH




17-5-2021 5:00 AM



ASSOCIATES
ARCHITECTS
11010 combe rd. ste. 210
AUBURN, CA 95602
530-268-3055
J. STEVE COLLOM
rhaarchitects.com
rhaassoc@bcglobal.net




A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
LOS ALTOS, CALIFORNIA
T2 VIEW STREET



1 UPPER FLOOR PLAN
A6 1/4" = 1'-0"



NORTH



drawings
revisions
project number 2559
date JULY 2, 2021
sheet number




15-5-2021 5:01 AM


EXTERIOR FINISH SCHEDULE		
LOCATION	KEYNOTE	MATERIAL/COLOR
ROOF	①	ARCHITECTURAL COMPOSITION SHINGLES
WALLS	②	HARDI HORIZONTAL SIDING
	③	HARDI SHINGLE SIDING
	④	STONE VENEER ADHERED METHOD
TRIM	⑤	WOOD TRIM
	⑥	ALUMINUM CLAD WOOD WINDOWS
WINDOWS	⑦	ALUMINUM CLAD WOOD FOLDING WINDOWS
	⑧	SOLID CORE ENTRY DOOR
	⑨	ALUMINUM CLAD FOLDING GLASS DOORS
	⑩	WOOD FRENCH DOOR(S)
DOORS	⑪	WOOD SLIDING DOOR(S)
	⑫	WOOD AND WROUGHT IRON RAILING
RAILINGS	⑬	SHAPED G.I. GUTTERS AND RECTANGULAR DOWNSPOUTS - PAINT
GUTTERS & DOWNSPOUTS	⑭	G.I. FLASHING - PAINT
FLASHING		



ASSOCIATES
ARCHITECTS
11010 combie rd. ste. 210
AUBURN, CA 95602
530-268-3055
J. STEVE COLLOM
rhaarchitects.com
rhaassoc@bcglobal.net

① RIGHT (NORTH) ELEVATION
3/16" = 1'-0"
0 1 3 4 10




② FRONT (EAST) ELEVATION
3/16" = 1'-0"
0 1 3 4 10



A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
LOS ALTOS, CALIFORNIA
T2 VIEW STREET

drawings	EXTERIOR ELEVATIONS
revisions	
project number	2559
date	JULY 2, 2021
sheet number	


A8



1 LEFT (SOUTH) ELEVATION
 A9 3/16" = 1'-0"



2 REAR (WEST) ELEVATION
 A9 3/16" = 1'-0"



EXTERIOR FINISH SCHEDULE		
LOCATION	KEYNOTE	MATERIAL/COLOR
ROOF	1	ARCHITECTURAL COMPOSITION SHINGLES
WALLS	2	HARDI HORIZONTAL SIDING
	3	HARDI SHINGLE SIDING
	4	STONE VENEER ADHERED METHOD
TRIM	5	WOOD TRIM
WINDOWS	6	ALUMINUM CLAD WOOD WINDOWS
	7	ALUMINUM CLAD WOOD FOLDING WINDOWS
DOORS	8	SOLID CORE ENTRY DOOR
	9	ALUMINUM CLAD FOLDING GLASS DOORS
	10	WOOD FRENCH DOOR(S)
	11	WOOD SLIDING DOOR(S)
RAILINGS	12	WOOD AND WROUGHT IRON RAILING
GUTTERS & DOWNSPOUTS	13	SHAPED G.I. GUTTERS AND RECTANGULAR DOWNSPOUTS - PAINT
FLASHING	14	G.I. FLASHING - PAINT

ASSOCIATES ARCHITECTS
 11010 combe rd. ste. 210
 AUBURN, CA 95602
 530-268-3055
 J. STEVE COLLOM
 rhaarchitects.com
 rhaassoc@bcglobal.net

LICENSED ARCHITECT
 J. STEVE COLLOM
 No. C 11982
 Exp. 10-21
 STATE OF CALIFORNIA

A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
 T2 VIEW STREET
 LOS ALTOS, CALIFORNIA

drawings
 EXTERIOR ELEVATIONS


revisions

project number
 2559


date
 JULY 2, 2021

sheet number


A9




ASSOCIATES
ARCHITECTS
11010 combie rd. ste. 210
AUBURN, CA 95602
530-268-3055
J. STEVE COLLOM
rhaarchitects.com
rhaassoc@bcglobal.net



A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
LOS ALTOS, CALIFORNIA
T2 VIEW STREET



(A) BUILDING SECTION/ELEVATION
3/16" = 1'-0"
0 1 3 6 10



(B) BUILDING SECTION/ELEVATION
3/16" = 1'-0"
0 1 3 6 10

drawings
BUILDING SECTION

revisions

project number
2559

date
JULY 2, 2021

sheet number

A10



64 VIEW STREET



60 VIEW STREET



54 VIEW STREET



69 VIEW STREET




71 VIEW STREET



77 VIEW STREET




100 MT. HAMILTON AVENUE



VIEW STREET

MT. HAMILTON AVENUE




152 MT. HAMILTON AVENUE



142 MT. HAMILTON AVENUE



126 MT. HAMILTON AVENUE



CONTEXT MAP

1" = 40'-0" 0 20 40 80 120

NORTH

ASSOCIATES ARCHITECTS
 11010 combie rd. ste. 210
 AUBURN, CA 95602
 530-268-3055
 J. STEVE COLLOM
 rhaarchitects.com
 rhaassoc@abglobal.net

A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREENE
 72 VIEW STREET
 LOS ALTOS, CALIFORNIA

drawings
CONTEXT MAP

revisions

project number
2559

date
JULY 2, 2021

sheet number

A11



June 30, 2021

Alan Grebene
72 View Street
Los Altos, California 94022

Re: Tree Assessment & Tree Protection Plan for 72 View Street

Dear Mr. Grebene,

This letter intends to address twenty-five (25) trees located on your property at 72 View Street in Los Altos, California (Exhibit 1.1). You have plans to renovate your house and the Community Development Department of Los Altos has asked to provide an arborist report that evaluates the potential impacts of the development, landscape plan, and grading and drainage plan on the on-site and immediate adjacent off-site trees. The report also prescribes the protection of any tree required to be either saved in conjunction with the development review application. This report does as such and evaluates all trees on the site and immediately adjacent to the site due to the proposed accessory dwelling unit being within the dripline of protected trees. No protected trees are proposed for removal and no directly adjacent off-site trees will be impacted. All on-site protected trees, defined as any tree 48-inches in circumference (>15-inches DBH) measured at 48-inches above grade, are proposed to be saved and preserved throughout the project.

The purpose of this letter is to help you ensure that the plans and construction are done in a manner consistent with Los Altos requirements for tree preservation. Provided in this letter are Tree Protection Guidelines.

I visited the site on June 23, 2021, to inspect the trees. All trees on-site are in good health and good structure.

Specific Tree Protection Measurements

- Tree 1 – Coast Live Oak – 36-inch DBH – Preserve (Low Impact)
Tree 2 – Coast Live Oak – 36-inch DBH – Preserve (Moderate Impact)
Tree 3 – Chinese Pistache – 12-inch DBH – Preserve (Low Impact)
Tree 4 – Chinese Pistache – 6-inch DBH – Preserve (Low Impact)
Tree 5 – Coast Live Oak – 12-inch DBH – Preserve (Moderate Impact)
Tree 6 – African Sumac – 6-inch DBH – Preserve (Low Impact)
Tree 7 – African Sumac – 8-inch DBH – Preserve (Moderate Impact)
Tree 8 – African Sumac – 8-inch DBH – Remove Due To Impacts (High Impact)
Tree 9 – Carrotwood – 8-inch DBH – Remove Due To Impacts (High Impact)
Tree 10 – Coast Live Oak – 36-inch DBH – Preserve (Moderate Impact)
Tree 11 – Japanese Maple – 6-inch DBH – Remove Due To Impacts (High Impact)
Tree 12 – Strawberry Madrone – 8-inch DBH – Preserve (Low Impact)
Tree 13 – Strawberry Madrone – 8-inch DBH – Preserve (Low Impact)

2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



- Tree 14 – Strawberry Madrone – 6-inch DBH – Preserve (Low Impact)
Tree 15 – Citrus – 6-inch DBH – Remove Due To Impacts (High Impact)
Tree 16 – Chinese Pistache – 10-inch DBH – Preserve (Low Impact)
Tree 17 – Chinese Pistache – 10-inch DBH – Preserve (Low Impact)
Tree 18 – Chinese Pistache – 10-inch DBH – Preserve (Low Impact)
Tree 19 – Chinese Pistache – 8-inch DBH – Preserve (Low Impact)
Tree 20 – Chinese Pistache – 10-inch DBH – Preserve (Low Impact)
Tree 21 – Chinese Pistache – 10-inch DBH – Preserve (Low Impact)
Tree 22 – Mayten – 12-inch DBH – Preserve (Low Impact)
Tree 23 – Mayten – 10-inch DBH – Preserve (Low Impact)
Tree 24 – Mayten – 10-inch DBH – Preserve (Low Impact)
Tree 25 – Mayten – 0-inch DBH – Preserve (Low Impact)

The objective of this section is to reduce the negative impacts of construction on the oak tree to an acceptable level. Trees vary in their ability to adapt to altered growing conditions, while mature trees have established stable biological systems in the preexisting physical environment. Disruption of this environment by construction activities interrupts the tree's physiological processes, causing depletion of energy reserves and a decline in vigor. This sometime is exhibited as death. Typically, this reaction may develop several years or more after disruption. Because of this deliberate care must be exercised during the construction process to mitigate any adverse effects.

The tree protection measures are intended to guide a construction project to ensure that appropriate practices will be implemented in the field to eliminate undesirable consequences that may result from uninformed or careless acts, and preserve both the tree and property values.

The following a required to be implemented along with the TPP:

- 1. The project arborist or contractor shall verify, in writing, that all preconstruction conditions have been met (tree fencing, erosion control, pruning, etc.)
2. The demolition, grading and underground contractors, construction superintendent and other pertinent personnel are required to meet with the project arborist at the site prior to beginning work to review procedures, tree protection measures and to establish haul routes, staging, areas, contacts, watering, etc.
3. Fenced enclosures shall be erected around trees to be protected to achieve three primary goals:
a. To keep the foliage crowns and branching structure of the trees to be preserved clear from contact by equipment, materials and activities;
b. Preserve roots intact and maintain proper soil conditions in a non-compacted state and;

2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



- c. To identify the tree protection zone (TPZ) in which no soil disturbance is permitted and activities are restricted.

Tree Protection Zone (TPZ)

The on-site tree shall have designated TPZs identifying the area sufficiently large enough to protect the tree and roots from disturbance. The recommended TPZ area can be determined by the canopy footprint. The TPZ shall be shown on all site plans for the project. The protective fencing shall serve as the TPZ boundaries.

Activities prohibited within the TPZ include:

- Storage or parking vehicles, building materials, refuse, excavated spoils or dumping of poisonous materials on or around trees and roots. Poisonous materials include, but are not limited to, paint, petroleum products, concrete or stucco mix, dirty water or any other material that may be deleterious to tree health.
The use of tree trunks as a winch support, anchorage, as a temporary power pole, signposts or other similar function.
Cutting of tree roots by utility trenching, foundation digging, placement of curbs and trenches and other miscellaneous excavation without prior approval of the project arborist.
Soil disturbance or grade/drainage changes

Activities permitted or required within the TPZ include:

- Mulching: During construction, wood chips shall be spread within the TPZ to a six (6) inch depth, leaving the trunk clear of mulch to help inadvertent compaction and moisture loss from occurring. The mulch may be removed if improvements or other landscaping is required. Mulch material shall be two (2) inch unpainted, untreated wood chip mulch or approved equal.
Root Buffer: When areas under the tree canopy cannot be fenced, a temporary buffer is required and shall cover the root zone and remain in place at the specified thickness until final grading stage.
Irrigation, aeration, fertilizing or other beneficial practices that have been specifically approved for use within the TPZ.

Size and type of fence

The fence shall consist of a six (6) foot high chain link fences. The fence is to be mounted on two-inch diameter galvanized iron posts, driven into the ground to a depth of at least two (2) feet at no

2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



more than ten (10) foot spacing. This detail shall appear on grading, demolition and improvement plans.

Types of Tree Protection for Project

- Type 1 Tree Protection: The fences shall enclose the entire area under the canopy dripline of the trees(s) to be saved throughout the life of the project.
For demolition of the brick wall, straw waddle shall be wrapped and secured around the trunk to protect against mechanical damage to the trunk. Once demoed, the fence can be installed at the exterior limit of the expansion, giving enough room for the building to be constructed.
Any fencing that must be relocated during the project may be supported by an appropriate grade level concrete base.
Duration of Tree Protection Fencing

Tree fencing shall be erected prior to demolition, grading or construction and remain in place until final inspection.

"Warning" Signage

Warning signs at a minimum size of 8.5x11-inches shall be prominently displayed on the fence. The sign shall clearly state:

WARNING - Tree Protection Zone - This fence shall not be removed and is subject to a penalty.

Pruning, Surgery and Removal

Prior to construction, the oak tree may require that branches be pruned clear from the existing and proposed structure, activities, building encroachment. Such pruning, surgery or the removal of trees shall adhere to the following standards:

- Pruning limitations:
Minimum Pruning: If the project arborist recommends that trees be pruned, and the type of pruning is left unspecified, the standard pruning shall consist of 'crown cleaning' as defined by ISA Pruning Guidelines. Trees shall be pruned to reduce hazards and develop a strong, safe framework.
Maximum Pruning: Maximum pruning should only occur in the rarest situation approved by the project arborist. No more than one-fourth (1/4) of the functioning leaf and stem area may be removed within one (1) calendar year of any tree, or removal of foliage so as to cause the unbalancing of the tree. It must be recognized that trees are individual in form and structure, and that pruning needs may not always

2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



fit strict rules. The project arborist shall assume all responsibility for special pruning practices that vary from the standards outlined in this TPP.

- Tree Workers: Pruning shall not be attempted by construction or contractor personnel, but shall be performed by a qualified tree care specialist or certified tree worker.

Activities During Construction & Demolition Near Trees

Soil disturbance or other injurious and detrimental activity within the TPZ is prohibited unless approved by the project arborist. If an injurious event inadvertently occurs, or soil disturbance has been specifically conditioned for project approval, then the following mitigation is required:

- Soil Compaction: If compaction of the soil occurs, it shall be mitigated as outlined in Soil Compaction Damage, and/or Soil Improvement.
Grading Limitations within the Tree Protection Zone:
Grade changes outside of the TPZ shall not significantly alter drainage to the tree.
Grade changes within the TPZ are not permitted.
Grade changes under specifically approved circumstances shall not allow more than six (6) inches of fill soil added or allow more than four (4) inches of existing soil to be removed from natural grade unless mitigated.

Trenching, Excavation and Equipment Use

Excavation or boring activity within the TPZ is restricted to the following activities, conditions and requirements if approved by the project arborist:

- Notification. Contractor shall notify the project arborist a minimum of twenty-four (24) hours in advance of the activity in the TPZ.
Root Severance. Roots that are encountered shall be cut to sound wood and repaired. Roots two (2) inches and greater must remain injury free.
Excavation. Any approved excavation, demolition or extraction of material shall be performed with equipment sitting outside the TPZ. Methods permitted are by hand digging, hydraulic or pneumatic air excavation technology. Avoid excavation within the TPZ during hot, dry weather.
a. If excavation or trenching for drainage, utilities, irrigation lines, etc., it is the duty of the contractor to tunnel under any roots two (2) inches in diameter and greater.

2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



- b. Prior to excavation for foundation/footings/walls, grading or trenching within the TPZ, roots shall first be severed cleanly one (1) foot outside the TPZ and to the depth of the future excavation. The trench must then be hand dug and roots pruned with a hand saw, reciprocating saw, narrow trencher with sharp blades or other approved root-pruning equipment.
Heavy Equipment. Use of backhoes, steel tread tractors or any heavy vehicles within the TPZ is prohibited

Root Severance

Cutting and removal of roots smaller than two (2) inches in diameter shall be done by chain saw or hand saw to provide a flat and smooth cut and cause the least damage possible to the root and tree's health. Cutting roots by means of tractor-type equipment or other than chain saws and handsaws is prohibited.

Proper pruning technique shall encourage callusing of the roots. Root cutting and removal shall not exceed thirty-five (35) percent of total root surface.

The Contractor shall remove any wood chips or debris that may be left over from root removal that may affect the construction of improvements as directed by the City Engineer.

If any roots over two (2) inches in diameter are severed during any excavation, the following procedure shall be followed:

- The roots shall be shaded by immediately covering the entire trench with plywood, or by covering the sides of the trench with burlap sheeting that is kept moist by watering twice per day.
When ready to backfill, each root shall be severed cleanly with a handsaw. Where practical, they should be cut back to a side root. Immediately, a plastic bag shall be placed over the fresh cut, and secured with a rubber band or electrical tape. Shading should immediately be placed until backfilling occurs.
Plastic bags shall be removed prior to backfilling.
Backfill shall be clean, native material free of debris, gravel or wood chips.

If roots three (3) inches in diameter, or larger, are encountered during excavation, Contractor shall contact the Public Works Construction Section and the City Parks Division immediately and request a field inspection by the Engineer and the City Tree Supervisor, or their designated representatives, and obtain instruction as to how the roots should be treated. No roots three (3) inches in diameter, or larger, shall be cut and removed without prior approval from the City Engineer and the City Tree Supervisor, or their designated representatives. Failure to notify the Public Works Department or the Parks Division for root inspection will result in the Contractor paying for damages and/or replacing the damaged tree as determined by the Engineer.

2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



Irrigation Program

Irrigate to wet the soil within the TPZ to a depth of twenty-four to thirty (24-30) inches at least once a month. Begin irrigating immediately prior to any construction activity. Alternatively, sub-surface irrigation may be used at regular specified intervals by injecting on approximate three (3) foot centers, ten (10) gallons of water per inch trunk diameter within the TPZ. Duration shall be until project completion or monthly until seasonal rainfall totals at least eight (8) inches of rain, unless specified otherwise by the project arborist.

Damage to Trees - Reporting

Any damage or injury to trees shall be reported within six (6) hours to the project arborist and job superintendent or City Arborist so that mitigation can take place. All mechanical or chemical injury to branches, trunk or to roots over two (2) inches in diameter shall be reported in the monthly inspection report. In the event of injury, the following mitigation and damage control measures shall apply:

- Root injury: If trenches are cut and tree roots two (2) inches or larger are encountered they must be cleanly cut back to a sound wood lateral root. The end of the root shall be covered with either a plastic bag and secured with tape or rubber band, or be coated with latex paint. All exposed root areas within the TPZ shall be backfilled or covered within one (1) hour. Exposed roots may be kept from drying out by temporarily covering the roots and draping layered burlap or carpeting over the upper three (3) feet of trench walls. The materials must be kept wet until backfilled to reduce evaporation from the trench walls.
Bark or trunk wounding: Current bark tracing and treatment methods shall be performed by a qualified tree care specialist within two (2) days.
Scaffold branch or leaf canopy injury: Remove broken or torn branches back to an appropriate branch capable of resuming terminal growth within five (5) days. If leaves are heat scorched from equipment exhaust pipes, consult the project arborist within six (6) hours.

Inspection Schedule

The project arborist retained by the applicant shall conduct the following required inspections of the construction site:

- Inspections shall verify that the type of tree protection and/or plantings re consistent with the standards outlined within this TPP. For each required inspection or meeting, a written summary of the changing tree related conditions, actions taken, and condition of trees shall be provided to the contractor.
Inspection of Protective Tree Fencing.


2337 AMERICAN AVE, HAYWARD, CA 94545 OFFICE: (888) 969-8733
1993 EAST BAYSHORE ROAD, REDWOOD CITY, CA 94063 CELL: (925) 518-2028
SOAKLEY@ARBORWELL.COM



- Pre-Construction Meeting. Prior to commencement of construction, the contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading equipment operators, and the project arborist.
Inspection of Rough Grading. The project arborist shall perform an inspection during the course of rough grading adjacent to the TPZ to ensure trees will not be injured by compaction, cut or fill, drainage and trenching, and if required, inspect aeration systems, tree wells, drains and special paving. The contractor shall provide the project arborist at least forty-eight (48) hours advance notice of such activity.
Monthly Inspections. The project arborist shall perform monthly inspections to monitor changing conditions and tree health. The City Arborist shall be in receipt of an inspection summary during the first week of each calendar month or, immediately if there are any changes to the approved plans or protection measures.
Any special activity within the Tree Protection Zone. Work in this area (TPZ) requires the direct on-site supervision of the project arborist.

Please review this information and contact me with any questions or concerns regarding the information provided in this letter.

Sincerely,
Sam Oakley, Arborwell
ISA Board Certified Master Arborist, WE-9474B TRAQ
ASCA Registered Consulting Arborist #556



ASSOCIATES ARCHITECTS
11010 combr rd. ste. 210
AUBURN, CA 95602
530-268-3055
J. STEVE COLLOM
rharchitects.com
rhassoc@rhaglobal.net



A PROPOSED RESIDENCE FOR:
ALAN & LAURA GREBENE
LOS ALTOS, CALIFORNIA
T2 VIEW STREET

drawings
ARBORIST REPORT

revisions


project number
2559

date
JULY 2, 2021

sheet number
AR1

- LEGEND**
- SSCO SANITARY SEWER CLEANOUT
 - SSMH SANITARY SEWER MANHOLE
 - X FENCE LINE
 - W WATER VALVE
 - WM WATER METER
 - Fire Hydrant symbol FIRE HYDRANT
 - Joint Pole symbol JOINT POLE
 - GUY ANCHOR symbol
 - TREE, SIZE AND TYPE AS NOTED
 - Gas Line symbol GAS LINE
 - Water Line symbol WATER LINE
 - CONCRETE symbol
 - GM GAS METER

- ABBREVIATIONS**
- FL FLOWLINE
 - TC TOP OF CURB
 - EP EDGE OF PAVEMENT
 - CONC CONCRETE
 - LIP LIP OF GUTTER
 - GS GROUND SHOT
 - AD AREA DRAIN
 - FF FINISH FLOOR
 - BSL BUILDING SETBACK LINE



SURVEYOR'S NOTE:


- UTILITIES FOUND ARE BASED UPON SURFACE EVIDENT FINDINGS. RECORDS OF UTILITIES WERE NOT UTILIZED FOR THIS SURVEY
- TREES SHOWN ARE THOSE OF SIZE SIGNIFICANCE. THE SITE CONTAINS OTHER TREES UNDER 6" AND ARE NOT SHOWN FOR MAP CLARITY. TREE CLASSIFICATIONS ARE TO THE BEST KNOWLEDGE OF THE SURVEYOR. AN ARBORIST MUST SPECIFY ACTUAL TREE TYPE.
- MAIN STRUCTURE AND APPURTENANT STRUCTURES ARE BASED UPON THE BEST EFFORTS OF THE SURVEY CREW. SOME ELEMENTS MAY BE MISSING AND CHECKS BY THE ARCHITECTS OFFICE WILL BE NECESSARY BEFORE DESIGN WORK.

BASIS OF BEARINGS

THE MONUMENT LINE OF W. EDITH AVENUE TAKEN AS N89°45'00"E, WAS ESTABLISHED FROM FOUND MONUMENTS IN W. EDITH AVENUE AT THE INTERSECTION OF SECOND STREET AND AT THE INTERSECTION OF THIRD STREET, AS SHOWN ON THAT CERTAIN TRACT NO., 5482 FILED IN BOOK 335 OF MAPS, AT PAGE 25, SANTA CLARA COUNTY RECORDS.

BENCHMARK
 SURVEY CONTROL POINT
 SET MAG NAIL
 ASSUMED ELEVATION=93.94'

BRIAN L. STOCKINGER
 PLS 6995
 EXPIRES 9-30-21



NRR ENGINEERING SERVICES CO.
 BRIAN L. STOCKINGER, PLS 6995
 535 WEYBRIDGE DRIVE, SAN JOSE, CA 95123
 (408) 348-7813
 nrengineering@yahoo.com

TOPOGRAPHICAL SURVEY
 72 VIEW STREET
 SANTA CLARA COUNTY
 CALIFORNIA

DATE	BY	OK	SCALE	DATE	DRAWN	CHECKED	PROJECT
			1"=10'	8-18-2020			


SHEET NO. **1**
 OF 1 SHEETS
 JOB NO. 72 VIEW STREET
 CAD FILE:

WATERPROOF G.F.C.I. JUNCTION BOX PER APPLICABLE CODE (LOCAL AND NATIONAL CODES AS APPLICABLE).


CONDUIT TO POWER SUPPLY PER MANUFACTURER AND APPLICABLE CODE (LOCAL AND NATIONAL CODES AS APPLICABLE).

30" HDPE CULVERT OR 30"x24" PRECAST CONCRETE DRAIN BOX

1/3 HP OR GREATER SUBMERSIBLE SUMP PUMP WITH INTEGRAL FLOAT SWITCH 12 HOUR DELAY PUMP SET @ SAME ELEVATION AS 6" PVC PIPE




SUMP WITH PUMP
N.T.S.




EARTH SWALE DETAIL
N.T.S.


- MAINTENANCE NOTES**
1. OWNER IS RESPONSIBLE FOR MAINTAINING ALL INLETS, RETENTION SYSTEM AND INFILTRATION DEVICE FROM TRASH, DEBRIS & SEDIMENTS.
 2. THE REGULAR CLEARING OF SILT AND DEBRIS IS ESPECIALLY IMPORTANT PRIOR TO EACH RAINY SEASON.




CATCH BASIN DETAIL
N.T.S.




ROOF DOWNSPOUT/SPLASH BLOCK
N.T.S.




INFILTRATION DEVICE TYPE 1 DETAIL
N.T.S.




STORMDRAIN CLEANOUT DETAIL
N.T.S.




PERMEABLE CONCRETE PAVERS-TRAFFIC
N.T.S.



INFILTRATION DEVICE TYPE 2 DETAIL
N.T.S.



AREA DRAIN DETAIL
N.T.S.



PERMEABLE CONCRETE PAVERS-PEDESTRIAN
N.T.S.




NR ENGINEERING
REGISTERED PROFESSIONAL ENGINEER
NAIM N. RAFFOUL
No. 56027
Exp. 12/31/22
CIVIL
STATE OF CALIFORNIA

**72 VIEW STREET
LOS ALTOS
CALIFORNIA**
APN: 167-36-025

MISC. DETAILS

REVISIONS	DATE

JOB NO:
DATE: 3-26-2021
SCALE: N.T.S.
DRAWN BY: NR
SHEET NO:




- NOTES:
1. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3'-5\"/>
 - 2. VERTICAL SPACING FOR SLOPE INSTALLATIONS:
 - 1:1 SLOPES = 10 FEET APART
 - 2:1 SLOPES = 20 FEET APART
 - 3:1 SLOPES = 30 FEET APART
 - 4:1 SLOPES = 40 FEET APART
 - <4:1 SLOPE = ONE ROW AT LOW POINT
 - 3. REMOVED SEDIMENT SHALL BE DEPOSITED IN AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT TO RUN OFF-SITE AND CAN BE PERMANENTLY STABILIZED.


Approved: *[Signature]*
City Engineer

REVISION		ENGINEERING DIVISION	
Description	Date		
		STRAW ROLLS	EC-4


STANDARD DETAILS MAY 2010



TEMPORARY COVER ON STOCK PILE
NTS




TEMPORARY CONCRETE WASHOUT FACILITY (ABOVE GRADE)
NTS



EROSION AND SEDIMENT CONTROL NOTES:

1. ALL CONSTRUCTION ACTIVITIES SHALL BE PERFORMED IN CONFORMANCE WITH THE STORM WATER POLLUTION PREVENTION PLAN FOR THIS PROJECT AND AS REQUIRED BY THE STATE OF CALIFORNIA WATER RESOURCES CONTROL BOARD ORDER R2-2003-0021 AND NPDES PERMIT NO. CAS 0029831.
2. THE DEVELOPER IS RESPONSIBLE FOR ENSURING THAT ALL CONTRACTORS AND SUBCONTRACTORS ARE AWARE OF ALL STORM WATER QUALITY MEASURES AND IMPLEMENT SUCH MEASURES. FAILURE TO COMPLY WITH THE APPROVED CONSTRUCTION BEST MANAGEMENT PRACTICES WILL RESULT IN THE ISSUANCE OF CORRECTION NOTICES, CITATIONS, AND/OR STOP ORDERS.
3. ANY VEHICLE OR EQUIPMENT WASHING/STEAM CLEANING MUST BE DONE AT AN APPROPRIATELY EQUIPPED FACILITY WHICH DRAINS TO THE SANITARY SEWER. OUTDOOR WASHING MUST BE MANAGED IN SUCH A WAY THAT THERE IS NO DISCHARGE OF SOAPS, SOLVENTS, CLEANING AGENTS OR OTHER POLLUTANTS TO THE STORM DRAINS. WASH WATER SHALL DISCHARGE TO THE SANITARY SEWER, SUBJECT TO REVIEW AND APPROVAL OF THE CITY ENGINEER.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LITTER CONTROL AND SWEEPING OF ALL PAVED SURFACES DURING CONSTRUCTION.
5. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 1 TO APRIL 30. EROSION CONTROL MEASURES ARE TO BE FUNCTIONAL PRIOR TO OCTOBER 1ST OF ANY YEAR GRADING OPERATIONS HAVE LEFT AREAS UNPROTECTED FROM EROSION.
6. ALL ON-SITE STORM DRAINS SHALL BE CLEANED IMMEDIATELY BEFORE THE START OF THE RAINY SEASON BEGINNING ON OCTOBER 1ST EACH YEAR, SUBJECT TO THE REVIEW OF THE BUILDING/ENGINEERING INSPECTOR.
7. IF RAINY WEATHER BECOMES IMMINENT, GRADING OPERATIONS SHALL BE STOPPED AND EROSION CONTROL MEASURES SHALL BE IMPLEMENTED TO PROTECT DISTURBED AREAS.
8. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT LADEN RUNOFF TO ANY STORM DRAIN SYSTEM.
9. CONSTRUCTION ENTRANCES SHALL CONSIST OF A MINIMUM 8\"/>
- 10. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL MEASURES ARE TO BE BLOCKED UNLESS THE AREA DRAINED IS UNDISTURBED OR STABILIZED.
- 11. BORROW AREAS AND TEMPORARY STOCKPILES SHALL BE PROTECTED WITH APPROPRIATE EROSION CONTROL MEASURES TO THE SATISFACTION OF THE CITY ENGINEER.
- 12. NO STRAW BALES OR SILT FENCES SHALL BE USED AS EROSION CONTROL MEASURES. SILT FENCES MAY ONLY BE USED AS A PHYSICAL BARRIER TO PREVENT VEHICULAR AND PEDESTRIAN TRAFFIC FROM USING NON-APPROVED ACCESS POINTS (E.G. - ALONG RIGHT-OF-WAY).
- 13. ALL DISTURBED AREAS INCLUDING FLAT PADS ARE TO BE TREATED WITH STRAW AND TACKIFIER AT A RATE OF 2 TONS PER ACRE APPROXIMATELY 3 INCHES THICK.



- NOTES:
1. THICKNESS OF FILLED BAGS WHEN LAID SHALL NOT EXCEED 4\"/>
 - 2. ENSURE THERE ARE NO GAPS BETWEEN THE BAGS.
 - 3. REMOVE ACCUMULATED SILT, AND DEBRIS BEFORE IT EXCEEDS 2\"/>
 - 4. INSPECT INLET PROTECTION DAILY DURING EXTENDED RAINFALL PERIODS AND BEFORE AND AFTER EACH RAIN EVENT.

BURLAP SACK DRAIN INLET (D.I.)
SEDIMENT FILTER DETAIL
NTS



NNR ENGINEERING
SERVICES CO.
500 WETBROOK DRIVE
SAN JOSE, CALIFORNIA 95028
(408) 946-7985

72 VIEW STREET
LOS ALTOS
CALIFORNIA


EROSION CONTROL
PLAN

REVISIONS	DATE

JOB NO:
DATE: 3-26-2021
SCALE: 1"=10'
DRAWN BY: NR
SHEET NO:

Heavy Equipment Operation

Best Management Practices for the Construction Industry



- Doing the Job Right**
- Site Planning and Preventive Vehicle Maintenance**
- Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks.
 - Perform major maintenance, repair jobs, and vehicle and equipment washing of site where cleaning is easier.
 - If you must drain and replace motor oil, radiator coolant, or other fluids on site, use drip pans or drop cloths to catch drips and spills. Collect all spent fluids, store in separate containers, and properly dispose as hazardous waste (recycle whenever possible).
 - Do not use diesel oil to lubricate equipment parts, or clean equipment. Use only water for any onsite cleaning.
 - Cover exposed fifth wheel hitches and other oily or greasy equipment during rain events.

Storm water Pollution from Heavy Equipment on Construction Sites

Poorly maintained vehicles and heavy equipment that leak oil, antifreeze or other fluids on the construction site are common sources of storm drain pollution. Prevent spills and leaks by isolating equipment from runoff channels, and by watching for leaks and other maintenance problems. Remove construction equipment from the site as soon as possible.

- Best Management Practices for the**
- Vehicle and equipment operators
 - Site supervisors
 - General contractors
 - Home builders
 - Developers

Landscaping, Gardening, and Pool Maintenance

Best Management Practices for the Construction Industry



- Doing The Right Job**
- General Business Practices**
- Protect stockpiles and landscaping materials from wind and rain by storing them under tarps or secured plastic sheeting.
 - Store pesticides, fertilizers, and other chemicals indoors or in a shed or storage cabinet.
 - Schedule grading and excavation projects during dry weather.
 - Use temporary check dams or ditches to divert runoff away from storm drains.
 - Protect storm drains with sandbags or other sediment controls.
 - Re-vegetation is an excellent form of erosion control for any site.
- Landscaping/Garden Maintenance**
- Use pesticides sparingly, according to instructions on the label. Rinse empty containers, and use rinse water as product. Dispose of rinsed, empty containers in the trash. Dispose of unused pesticides as hazardous waste.
 - Collect lawn and garden clippings, pruning waste, and trim trimmings. Chip if necessary, and compost.
 - In communities with curbside pick-up of yard waste, place clippings and pruning waste at the curb in approved bags or containers. Or, take to a landfill that composts yard waste. No curbside pickup of yard waste is available for commercial properties.


Storm Drain Pollution From Landscaping and Swimming Pool Maintenance

Many landscaping activities expose soils and increase the likelihood that earth and garden chemicals will run off into the storm drains during irrigation or when it rains. Swimming pool water containing chlorine and copper-based algicides should never be discharged to storm drains. These chemicals are toxic to aquatic life.

- Best Management Practices for the**
- Landscapers
 - Gardeners
 - Swimming pool/spa service and repair workers
 - General contractors
 - Home builders
 - Developers
 - Homeowners

General Construction And Site Supervision

Best Management Practices For Construction



- Doing The Job Right**
- General Principles**
- Keep an orderly site and ensure good housekeeping practices are used.
 - Maintain equipment properly.
 - Cover materials when they are not in use.
 - Keep materials away from streets, storm drains and drainage channels.
 - Ensure dust control water doesn't leave site or discharge to storm drains.
- Advance Planning To Prevent Pollution**
- Schedule excavation and grading activities for dry weather periods. To reduce soil erosion, plant temporary vegetation. Place other erosion controls before rain begins. Use the Erosion and Sediment Control Manual, available from the Regional Water Quality Control Board, as a reference.
 - Control the amount of runoff crossing your site (especially during excavation) by using berms or temporary or permanent drainage ditches to divert water flow around the site. Reduce storm water runoff velocities by constructing temporary check dams or berms where appropriate.
 - Train your employees and subcontractors. Make these best management practices available to everyone who works on the construction site. Inform subcontractors about the storm water requirements and their own responsibilities.
- Good Housekeeping Practices**
- Designate one area of the site for auto parking, vehicle refueling, and routine equipment maintenance. The designated area should be well away from streams or storm drain inlets, berms if necessary. Make major repairs off site.
 - Keep materials out of the rain - prevent runoff contamination at the source. Cover exposed piles of soil or construction materials with plastic sheeting or temporary roofs. Before it rains, sweep and remove materials from surfaces that drain to storm drains, creeks, or channels.
 - Keep pollutants off exposed surfaces. Place trashcans and recycling receptacles around the site to minimize litter.

- Best Management Practices for the**
- General contractors
 - Site supervisors
 - Inspectors
 - Home builders
 - Developers

Storm Drain Pollution from Construction Activities

Construction sites are common sources of storm water pollution. Materials and wastes that blow or wash into a storm drain, gutter, or street have a direct impact on local creeks and the Bay. As a contractor, or site supervisor, owner or operator of a site, you may be responsible for any environmental damage caused by your subcontractors or employees.

Roadwork and Paving

Best Management Practices for the Construction Industry



- Doing The Job Right**
- General Business Practices**
- Develop and implement erosion/sediment control plans for roadway embankments.
 - Schedule excavation and grading work during dry weather.
 - Check for and repair leaking equipment.
 - Perform major equipment repairs at designated areas in your maintenance yard, where cleanup is easier. Avoid performing equipment repairs at construction sites.
 - When refueling or when vehicle/equipment maintenance must be done on site, designate a location away from storm drains and creeks.
 - Do not use diesel oil to lubricate equipment parts or clean equipment.
 - Recycle used oil, concrete, broken asphalt, etc. whenever possible, or dispose of properly.
- During Construction**
- Avoid paving and seal coating in wet weather, or when rain is forecast, to prevent fresh materials from contacting stormwater runoff.
 - Cover and seal catch basins and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
 - Protect drainage ways by using earth dikes, sand bags, or other controls to divert or trap and filter runoff.

Best Management Practices for the

- Road crews
- Driveway/sidewalk/parking lot construction crews
- Seal coat contractors
- Operators of grading equipment, paving machines, dump trucks, concrete mixers
- Construction inspectors
- General contractors
- Home builders
- Developers

Storm Drain Pollution from Roadwork

Road paving, surfacing, and pavement removal are common sources of storm drain pollution. Roadwork activities that are not properly controlled can contribute to storm drain pollution. Roadwork activities that are properly controlled can help prevent storm drain pollution. Roadwork activities that are properly controlled can help prevent storm drain pollution.

Painting and Application of Solvents and Adhesives

Best Management Practices for the Construction Industry



- Doing The Job Right**
- Handling Paint Products**
- Keep all liquid paint products and wastes away from the gutter, street, and storm drains. Liquid residues from paints, thinners, solvents, glues, and cleaning fluids are hazardous wastes and must be disposed of at a hazardous waste collection facility (contact your local stormwater program listed on the back of this brochure).
 - When thoroughly dry, empty paint cans, used brushes, rags, and drop cloths may be disposed of as garbage in a sanitary landfill. Empty, dry paint cans also may be recycled as metal.
 - Wash water from painted buildings constructed before 1978 can contain high amounts of lead, even if paint chips are not present. Before you begin stripping paint or cleaning pre-1978 building exteriors with water under high pressure, test paint for lead by taking paint scrapings to a local lead lab. See "Yellow Pages" for a state-certified laboratory.
 - If there is loose paint on the building, or if the paint tests positive for lead, block storm drains. Check with the wastewater treatment plant to determine whether you may discharge water to the sanitary sewer, or if you must send it offsite for disposal as hazardous waste.

Storm Drain Pollution from Paints, Solvents, and Adhesives

All paints, solvents, and adhesives contain chemicals that are harmful to wildlife in local creeks, San Francisco Bay, and the Pacific Ocean. Toxic chemicals may come from liquid or solid products or from cleaning residues or rags. Paint material and wastes, adhesives and cleaning fluids should be recycled whenever possible, or disposed of properly to prevent these materials from flowing into storm drains and watercourses.

- Best Management Practices for the**
- Homeowners
 - Painters
 - Paperhangers
 - Plasterers
 - Graphic artists
 - Dry wall crews
 - Floor covering installers
 - General contractors
 - Home builders
 - Developers

Fresh Concrete and Mortar Application

Best Management Practices for the Construction Industry



- Doing The Job Right**
- General Business Practices**
- Wash out concrete mixers only in designated wash-out areas in your yard, away from storm drains and waterways, where the water will flow into a temporary waste pit in a dirt area. Let water percolate through soil and dispose of settled, hardened concrete as garbage. Whenever possible, recycle washout by pumping back into mixers for reuse.
 - Wash out chutes onto dirt areas at site that do not flow to streets or drains.
 - Always store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Protect dry materials from wind.
 - Secure bags of cement after they are open. Be sure to keep wind-blown cement powder away from streets, gutters, storm drains, rainfall, and runoff.
 - Do not use diesel fuel as a lubricant on concrete forms, tools, or trailers.

Storm Drain Pollution from Fresh Concrete and Mortar Applications

Fresh concrete and cement-related mortars that wash into lakes, streams, or estuaries are toxic to fish and the aquatic environment. Disposing of these materials to the storm drains or creeks can block storm drains and create serious problems, and is prohibited by law.

- Best Management Practices for the**
- Masons and bricklayers
 - Sidewalk construction crews
 - Patio construction workers
 - Construction inspectors
 - General contractors
 - Home builders
 - Developers
 - Concrete delivery/pumping workers

Preventing Pollution: It's Up to Us

In the Santa Clara Valley, storm drains transport water directly to local creeks and San Francisco Bay without treatment. Storm water pollution is a serious problem for wildlife dependent on our waterways and for the people who live near polluted streams or bay lands. Some common sources of this pollution include spilled oil, fuel, and fluids from vehicles and heavy equipment; construction debris; sediment created by erosion; landscaping runoff containing pesticides or weed killers; and materials such as used motor oil, antifreeze, and paint products that people pour or spill into a street or storm drain. Thirteen valley municipalities have joined together with Santa Clara County and the Santa Clara Valley Water District to educate local residents and businesses and fight storm water pollution. To comply with this program, contractors most comply with the practices described in this drawing sheet.

Spill Response Agencies

DIAL 9-1-1
State Office of Emergency Services Warning Center (24 hours): 800-852-7550
Santa Clara County Environmental Health Services: (408) 299-6930

Local Pollution Control Agencies

County of Santa Clara Pollution Prevention Program: (408) 441-1195
County of Santa Clara Integrated Waste Management Program: (408) 441-1198
County of Santa Clara District Attorney Environmental Crimes Hotline: (408) 299-TIPS
Santa Clara County Recycling Hotline: 1-800-533-8414
Santa Clara Valley Water District: (408) 265-2600
Santa Clara Valley Water District Pollution Hotline: 1-888-510-5151
Regional Water Quality Control Board San Francisco Bay Region: (510) 622-2300
Palo Alto Regional Water Quality Control Plant: (650) 329-2598
Serving East Palo Alto Sanitary District, Los Altos, Los Altos Hills, Mountain View, Palo Alto, Stanford
City of Los Altos
Building Department: (650) 947-2752
Engineering Department: (650) 947-2780




Los Altos Municipal Code Requirements

- Los Altos Municipal Code Chapter 10.08.390 Non-storm water discharges**
- Unlawful discharges. It shall be unlawful to discharge any domestic waste or industrial waste into storm drains, gutters, creeks, or San Francisco Bay. Unlawful discharges to storm drains shall include, but not be limited to, discharge from toilets; sinks; industrial processes; cooling systems; boilers; fabric cleaning; equipment cleaning; vehicle cleaning; construction activities, including, but not limited to, painting, paving, concrete placement, saw cutting and grading; swimming pools; spas; and fountains, unless specifically permitted by a discharge permit or unless exempted pursuant to guidelines published by the superintendent.
 - Threatened discharges. It shall be unlawful to cause hazardous materials, domestic waste, or industrial waste to be deposited in such a manner or location as to constitute a threatened discharge into storm drains, gutters, creeks or San Francisco Bay. A "threatened discharge" is a condition creating a substantial probability of harm, when the probability and potential extent of harm make it reasonably necessary to take immediate action to prevent, reduce or mitigate damages to persons, property or natural resources. Domestic or industrial wastes that are no longer contained in a pipe, tank or other container are considered to be threatened discharges unless they are actively being cleaned up.
- Los Altos Municipal Code Section 10.08.430 Requirements for construction operations.**
- A spill response plan for hazardous waste, hazardous materials and uncontained construction materials shall be prepared and available at the construction sites for all projects where the proposed construction site is equal to or greater than one acre of disturbed soil and for any other projects for which the city engineer determines it is necessary to protect surface waters. Preparation of the plan shall be in accordance with guidelines published by the city engineer.
 - A storm water pollution prevention plan shall be prepared and available at the construction sites for all projects greater than one acre of disturbed soil and for any other projects for which the city engineer determines that a storm water management plan is necessary to protect surface waters. Preparation of the plan shall be in accordance with guidelines published by the city engineer. Prior approval shall be obtained from the city engineer or designee to discharge water pumped from construction sites to the storm drain. The city engineer or designee may require gravity settling and filtration upon a determination that either or both would improve the water quality of the discharge. Contaminated groundwater or water that exceeds state or federal requirements for discharge to navigable waters may not be discharged to the storm drain. Such water may be discharged to the sewer, provided that the requirements of Section 10.08.240 are met and the approval of the superintendent is obtained prior to discharge.
 - No cleanup of construction debris from the streets shall result in the discharge of water to the storm drain system; nor shall any construction debris be deposited or allowed to be deposited in the storm drain system. (Prior code § 5-5.643)
- Criminal and judicial penalties can be assessed for non-compliance.

Earth-Moving And Dewatering Activities

Best Management Practices for the Construction Industry



- Doing The Job Right**
- General Business Practices**
- Schedule excavation and grading work during dry weather.
 - Perform major equipment repairs away from the job site.
 - When refueling or vehicle/equipment maintenance must be done on site, designate a location away from storm drains.
 - Do not use diesel oil to lubricate equipment parts, or clean equipment.
- Practices During Construction**
- Remove existing vegetation only when absolutely necessary. Plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
 - Protect down slope drainage courses, streams, and storm drains with wattles, or temporary drainage swales. Use check dams or ditches to divert runoff around excavations. Refer to the Regional Water Quality Control Board's Erosion and Sediment Control Field Manual for proper erosion and sediment control measures.

Storm Drain Pollution from Earth-Moving Activities and Dewatering

Soil excavation and grading operations loosen large amounts of soil that can flow or blow into storm drains when handled improperly. Sediments in runoff can clog storm drains, smother aquatic life, and destroy habitats in creeks and the Bay. Effective erosion control practices reduce the amount of runoff crossing a site and slow the flow with check dams or roughened ground surfaces. Contaminated groundwater is a common problem in the Santa Clara Valley. Depending on soil types and site history, groundwater pumped from construction sites may be contaminated with toxic (such as oil or solvents) or laden with sediments. Any of these pollutants can harm wildlife in creeks or the Bay, or interfere with wastewater treatment plant operation. Discharging sediment-laden water from a dewatering site into any water of the state without treatment is prohibited.

- Best Management Practices for the**
- Bulldozer, back hoe, and grading machine operators
 - Dump truck drivers
 - Site supervisors
 - General contractors
 - Home builders
 - Developers


Blueprint for a Clean Bay

Remember: The property owner and the contractor share ultimate responsibility for the activities that occur on a construction site. You may be held responsible for any environmental damage caused by your subcontractors or employees.

Best Management Practices for the Construction Industry



Santa Clara Urban Runoff Pollution Prevention Program



DESIGNED BY: LARRY LIND	APPROVED BY: 	CITY OF LOS ALTOS	DATE: OCTOBER, 2003
DRAWN BY: VICTOR CHEN	CITY ENGINEER	48056 R.C.L.	SCALE: N.T.S.
CHECKED BY: JIM GUSTAFSON	SHEET	OF	SHEETS
DRAWING NO.			DRAWING NO.



NR ENGINEERING SERVICES CO.
SERVICES CO.
5500 VERDE DRIVE
SAN FRANCISCO, CALIFORNIA 94133
(415) 947-7383

72 VIEW STREET
LOS ALTOS
CALIFORNIA
APN: 167-06-025

BLUEPRINT FOR A
CLEAN BAY

REVISIONS	DATE
JOB NO:	
DATE:	3-26-2021
SCALE:	N.T.S.
DRAWN BY:	NR
SHEET NO:	

Plant Legend

BOTANICAL	COMMON	QTY	SIZE	WATER	REMARKS
Tree					
<i>Acer palmatum</i> 'Red Emperor'	Red Emperor Japanese Maple	1	24" Box	Medium	
<i>Luma apiculata</i>	Luma	1	15 Gallon	Medium	Prairie Fire
<i>Malus floribunda</i>	Japanese Flowering Crabapple	1	15 Gallon	Medium, Extra in Summer	
<i>Olea europaea</i> 'Swan Hill'	Swan Hill Fruitless Olive	1	24" Box	Very Low, Medium	
<i>Podocarpus gracilior</i>	Fern Pine	1	15 Gallon	Low, Medium	
<i>Prunus caroliniana</i>	Carolina Laurel Cherry	3	5 Gallon	Low	
Shrub					
<i>Heteromeles arbutifolia</i>	Toyon	3	5 Gallon	Very Low, Low	
<i>Rosmarinus officinalis</i> 'Tuscan Blue'	Tuscan Blue Upright Rosemary	5	5 Gallon	Very Low, Extra in Summer	

Screening Species Photos



Olea europaea 'Swan Hill'
Fruitless Olive 24" Box
4-5-6' x 3-4' (Height x Width)
<25' x <25' (At Maturity)
Growth Rate: Moderate



Luma apiculata
Luma Tree 24" Box
4-5' x 2-3' (Height x Width)
6-12' x 6-8' (At Maturity)
Growth Rate: Moderate



Acer palmatum 'Emperor 1'
Red Emperor Japanese Maple 24" Box
6-8' x 3-4' (Height x Width)
20-25' x 15-20' (At Maturity)
Growth Rate: Moderate, Slow



Malus floribunda 'Prairie fire'
Prairiefire Crabapple 15 Gal.
5-6' x 2-3' (Height x Width)
12' x 18' (At Maturity)
Growth Rate: Moderate



Prunus caroliniana
Carolina Laurel Cherry 5 Gal.
2-3' x 12-16" (Height x Width)
8-10' x 6-8' (At Maturity)
Growth Rate: Moderate to Fast



Podocarpus gracilior
Fern Pine 15 Gal.
5-6' x 16-20" (Height x Width)
30-50' x 15-20' (At Maturity)
Growth Rate: Slow



Heteromeles arbutifolia
Toyon 5 Gal.
12-14" x 12-14" (Height x Width)
6-20' x 6-10' (At Maturity)
Growth Rate: Moderate



REVISIONS	BY
1	07-02-21 KAA




KAREN AITKEN & ASSOCIATES
LANDSCAPE ARCHITECTS
8262 Rancho Real Gilroy Ca. 95020
Calif. Reg.#2239 (408) 842-0245
karen@k.a.design

GREBENE RESIDENCE
72 View Street, Los Altos, CA.
LANDSCAPE PLAN



DATE	07-02-21
SCALE	1"=10'-0"
DRAWN	SL-EM
JOB	GREBENE

L-1



* NOTES (E) = Existing